

RATIFIED BY THE BERRIEN COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990

RECORDED

Berrien County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Nov 29 3 53 PM '95

Daniel B. Zwar
 6-22-95
 For corners in Berrien (County)

Daniel B. Zwar
 REGISTER OF DEEDS
 BERRIEN COUNTY, MICHIGAN

For corners in	Located In:	Corner Code #
1. Public Land Survey	T <u>4S</u> R <u>18W</u>	<u>M-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

11/29/95 111W2015 \$66
 CORNER \$7.00
 11/29/95 111W2015 \$66
Register of Deeds Stamp & File Number
 STATE RECORR FEE \$2.00

I, Daniel B. Zwar, in a field survey on November 13, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1827 Wm. Brookfield set corner post to 24 & 25 Beech 14 N71°W-9 Links Beech 8 S30°W-32 Links
 1945 (from E.R. Stefan library) Dewey?
 A) SE corner of Sec 24-4-18 Stone & Brick
 B) SW corner of Sec 19-4-17 Plug
 "A" is 76.8' south of "B"

1972 R. Garrett SE corn sec 24-4-18 Stone with Brick
 6" Hickory S5°W 21.9' Utility Pole N5°E 24.9'
 SW corner Sec 19-4-17 N 76.8'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

November 13, 1995 found pointed stone surrounded by pieces of red brick. Measured 76.84' feet North to SW corner of section 19-4-17, verified.

SURVEY & REMONUMENTATION


MAR 27 1996

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Witnessed point on stone, removed and replaced at exact location with standard 3'X4" dia. concrete monument and brass BCRP cap. Left Bricks surrounding monument. Corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Witnesses:
 set nail w/washer in 12" Maple N46°E 32.85'
 set nail w/washer in 6" Maple S 50°E 20.99'
 set nail w/washer in 15" Twin Ash S32°W 22.39'
 SW corner Section 19-4-17 North 76.84'



Signed by Daniel B. Zwar Date Nov 29, 1995
 Surveyor's Michigan License No. 28435