

**SURVEY &
REMONUMENTATION**

12/29/93

11145256 A66
CORNER \$7.00
11145256 A66
STATE REFIN FEE \$2.00

FEB 17 1994

**Berrien County Remonumentation Program
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

COMMISSION

For corners in

<u>Berrien</u> (County)	Located In:	Corner Code ##
1. Public Land Survey	T <u>4S</u> R <u>19W</u>	<u>I-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

DEC 29 3 19 PM '93

Berrien County
REGISTER OF DEEDS
BERRIEN COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Charles W. Barger, in a field survey on December 29, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Octogonal iron in Monument Box
CB S70°E 44.7'
CB N89°W 23.7'
Hydrant N21°E 87.2'
10" Pine N31°W 57.5'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Same as in paragraph A

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced octogonal iron with 1" iron pipe 3' long and capped with 2-1/2" brass remonumentation cap in monument box.
CB n89°w 23.7'
Manhole N42.5°E 25.4'
Hydrant N21°E 87.2'
Power Pole #B229-119 S61.5°W 32.45'



Signed by Charles W. Barger P.S.

Date December 29, 1993

Surveyor's Michigan License No. 31589