

**SURVEY &  
REMONUMENTATION**

FEB 17 1994

12/29/93  
12/29/93

111#5256 A66  
CORNER \$7.00  
STATE RECOR FEE \$2.00

**COMMISSION**

**Berrien County Remonumentation Program  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

For corners in

<u>Berrien</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>4S</u> R <u>19W</u>	<u>J-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

DEC 29 3 19 PM '93

*Bernice T. ...*  
REGISTER OF DEEDS  
BERRIEN COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Charles W. Barger, in a field survey on December 29, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

3/4" iron pipe in Monument Box  
Hydrant S50°E 59.5'  
Manhole East 19.4'  
Manhole N30°W 14.3'  
CB N50°E 57.0'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

3/4" iron pipe in Monument Box  
Hydrant S50°E 59.5'  
Manhole East 19.4'  
Manhole N30°W 14.3'  
CB N50°E 57.0'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced 3/4" iron pipe with 3' long 1" iron pipe with 2-1/2" diameter brass remonumentation cap in monument box.  
Manhole N30°W 14.3'  
Manhole East 19.4'  
CB S49°E 54.2'  
CB S39°W 55.4'



Signed by Charles W. Barger P.S. Date December 29, 1993  
Surveyor's Michigan License No. 31589