

T5S, R17W

H-3 N¹/₄ COR, SEC 10.
 FOUND LARGE BOLT
 SE, 25.12, 8" APPLE, PK
 NE, 18.67, 4" SASSAFRASS, PK
 EAST, 5', EDGE RD.

G-4 W¹/₄ COR, SEC 10
 FOUND 3/4" PIPE W/PLASTIC
 CAP (SET BY SOUTHWEST SURVEYING)
 ALTON HOWARD - 2382, PROJECTION
 FROM E¹/₄ COR. THRU CENTER SEC.

F-2 C¹/₄ COR, SEC 4
 FOUND CULTIVATOR TOOTH
 1" BELOW SURFACE, POINT
 UP, AT INTERSECTION OF
 FENCE NORTH & WEST

COR 16, SEC 4
 FOUND ROTTED 3" POST
 SURROUNDED BY BRICK AS
 MARKED FOR IN OLD WITNESS

G-2 E¹/₄ COR, SEC 4
 WEST, 12.0', 24" ELM, NAIL
 S50°W, 9.0', 24" ELM, NAIL
 (FROM SOUTHWEST SURVEYS - WATERVIEW)
 FOUND 1/2" PIPE IN E-W

F-3 S¹/₄ COR, SEC 4
 FD. PLOW POINT W/ 3/4" PIPE
 BESIDE IT. OLD WITNESSES.
 PLOW POINT 12" BELOW SURFACE
 16" THICK.
 N 35°E, 122.7', (90NS)

S-3 SE COR, SEC 4
 OLD WITNESSES CALL FOR STONE
 WITH 2" OR 3" WOOD POST (ROTTED)
 WITH BROKEN BRICK AROUND IT

FENCE SET BY ALTON HOWARD.
 S 12°W, 39.76', 8" MAPLE, PK + TAG
 S 78°W, 21.13, 7" " " "
 S 76°E, 29.24, 12" MAPLE IN CLUMP, ""

WEST 268.8', 12' ASH
 1/4" X 6' GUARD PIPE
 S 14°W, 76.12', 14" POPLAR,
 IN CLUMP, PK + TAG

SMALL ROUND STONE (6" X 10")
 FOUND ON SIDE NEAR COR.
 MARKED 3/4" PIPE WITH BRICK
 AND STONE AROUND.

COR 8, SEC 3
 N 45°E, 42.3', STREET SIGN
 N 45°W, 55.0', STOP SIGN
 S 30°W, 63.3, 36" MAPLE, NAIL

H-2
 C¹/₄ COR, SEC 3
 N 45°E, 48.8', 40" OAK, NAIL
 S 40°W, 120.3', NE COR CHIMNEY
 S 45°E, 53.45', STOP SIGN

S 76°E, 19.81', 40" MAPLE
 N 13°W, 12.18', 6" ELM
 S 56°W, 35.24', 9" OAK