

**SURVEY &
REMONUMENTATION**

APR 26 1995

RECORDED

RATIFIED BY THE BERRIEN COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER MICHIGAN
PUBLIC ACT 345 OF 1990

COMMISSION
REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Nov 23 3 05 PM '94

Berrien County Treasury
REGISTER OF DEEDS
BERRIEN COUNTY MICHIGAN

[Signature]
10-27-94
For corners in
BERRIEN
(County)

	Located In:	Corner Code ##
1. Public Land Survey	T <u>5S</u> R <u>17W</u>	<u>E-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, V.J. Strebs, in a field survey on November 17, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|--|---|
| 1827 - William Brookfield, D.S. (set Closing corner 82 links east of S.E. Cor, Sec. 32-4-17)
W. Oak 7 - S84°W - 24 Links
W. Oak 7 - S38°E - 41 Links | 1917 - Dewey
Set S.W. Cor. Sec. 33-4-17,
52' West of Stone at N.E.
Cor of Sec 5-5-17 |
| 1890 - Luther Hemingway
(set stone no witness) | 1986 - V.J. Strebs
Found Stone W/Cross |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Stone W/cross on top
Distance from North ¼ Cor. Sec 5-15-17 to Northeast Corner
Sec 5-5-17 - 1890 Luther Hemingway = 40.52 chains
(2674.32)
Recent Measurement = 2674.50'

11/23/94	111#7594	A66
	CORNER	\$7.00
11/23/94	111#7594	A66
	STATE REMON FEE	\$2.00

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.
SET 4" Dia concrete monument with B.C.R.P. Brass cap.
Nail & Witness tag in 10" Oak - West - 165.04'
Nail & Witness tag in 12" Triple Elm - S40°E - 103.67'
1½" Iron Pipe - S55°W - 39.80'
Concrete Monument W/B.C.R.P. Brass cap (S.E. Cor Sec. 32-4-17)
West - 54.12'

Signed by *[Signature]*
Surveyor's Michigan License No. 26469



Date 21 NOVEMBER 1994