

**SURVEY & REMONUMENTATION**

DEC 08 1993

**COMMISSION**

BERRIEN CO. REMONUMENTATION

11/29/93

11/29/93

111#2802 A33  
CORNER \$7.00  
111#2802 A33  
STATE REMON FEE \$2.00

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Berrien

(County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>5S</u>	R	<u>18W</u>	<u>A-7</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	_____
	S	_____	T	_____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

RECORDED  
 NOV 29 10 22 AM '93  
 Berrien County  
 REGISTER OF DEEDS  
 MEMBER OF THE NATIONAL BOARD OF SURVEYORS

Register of Deeds Stamp & File Number

I, Donald R. Pitts, Jr., in a field survey on November 12, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:  
A-7 Section Corner 18 & 19 T5S R18W

1829 August - Deputy Survey Lucius Lyon intersected W. Boundary 24 N. of Post.  
Sugar 18 N27E 4, Beech 13 S63E 49  
1948-1960- Berrien Co. Road Commission -Iron  
1987, - J.L. Quist Iron in Mon Box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-7 Section Corner 18 & 19 T5S, R18W


Found Iron Rod in Mon Box. Found Railroad Spike T5S, R19W, M-7, South 15.84', and is accepted as a careful and faithful reestablishment of the position of the original corner, and ratified by the Berrien County Remonumentation Program Peer Group on November 8, 1993.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-7 Section Corner 18 & 19 T5S, R18W

36" Long Iron Pipe with Berrien Co. Remon. Brass Cap in Mon Box.  
Nail & Wit Tag SW Side Power Pole B297.20 S40°W 41.95'  
Nail & Wit Tag SW Side Power Pole S45°E 45.54'  
Nail & Wit Tag NE Side 12° Oak N50°W 73.42'  
36" Long Iron Pipe with Berrien Co. Remon. Cap in Mon Box, T5S, R19W, M-7 South 15.84'

Signed by Donald R. Pitts, Jr.  
Surveyor's Michigan License No. 25867



Date 28 November 1993