

**SURVEY & REMONUMENTATION**

DEC 08 1993

**COMMISSION**

**BERRIEN CO. REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED-

Nov 17 1 43 PM '93

*Bernice T. ...*  
REGISTER OF DEEDS  
BERRIEN COUNTY MICHIGAN

For corners in

Berrien  
(County)

Located In: Corner Code ##

- 1. Public Land Survey T 5S R 18W A-9  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

I, Donald R. Pitts, Jr., in a field survey on November 15, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**


A. Description of original monument and accessories and/or subsequent restoration:

A-9 Original government surveyors intersected west boundary of T5S, R18W 34 Links North of Post

11/17/93 111#2096 A66  
CORNER \$7.00  
11/17/93 111#2096 A66  
STATE REMON FEE \$2.00

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-9 Found State of Michigan Mounment in Mon Box.  
State of Michigan Mounment in Mon Box T5S R19W M-9 South 22.73'



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-9 Section Corner 19 & 30 T5S, R18W Pulled State of Michigan Mon & Set 7" Long Iron Pipe w/BC Re-mon Brass Cap in Mon Box with Mortar and is accepted as a careful and faithful perpetuation of the original corner.  
Nail & Wit Tag N.E. Side power Pole B297 48N 22° W 58.55'  
Nail & Wit Tag S.W. Side power Pole B315 28S 25° W 62.41'  
S.E. Cor Bldg N80° W 78.11'  
7" Long Iron Pipe w/B.C. Re-mon Brass Cap in Mon Box with Mortar T5S, R19W M-9 South 22.73'

Signed by Donald R. Pitts, Jr. Date 11/17/93  
Surveyor's Michigan License No. 25867