

RATIFIED BY THE BERRIEN COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER MICHIGAN
PUBLIC ACT 345 OF 1990

RECORDED

**Berrien County Remonumentation Program
LAND CORNER RECORDATION CERTIFICATE**

00 NOV -8 PM 12:51

7-06-00
Filing Requirement of Act 74, Mich. P.A. 1970

GRAND TRENTHWAY
REGISTER OF DEEDS
BERRIEN COUNTY, MICHIGAN

For corners in

Berrien (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>5S</u> R <u>18W</u>	<u>J-1</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

11/08/00 111#6048 A66
CORNER \$7.00
11/09/00 111#6048 A66
STATE REMON FEE \$2.00

Register of Deeds Stamp & File
Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Alan K. Bartlett, in a field survey on March 29, 2000
do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the
corner points mentioned in lines 1 and 2 above were in conformance with
regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and /or that the corner points
mentioned in lines 3, 4 and 5 above were in conformance with the rules of the
Michigan Board of Land Surveyors or by a Decree of a Court of Law;
established, re-established, monumented, recovered, found as expressed
below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	10			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

NOT SET AS ORIGINAL GOVERNMENT CORNER
1879- COUNTY SURVEY BOOK; STONE 2' 3" LONG AND 4 BIRCH 10x7
1929- H.L.D. FOUND STONE
1952- LAUKUS, SPRAGUE; STONE 21.45' JOG WEST TO S/14 SECTION 35
1973- E.R. STEFAN; 1/2 MILE DISTANCE EAST=2635.70', ANGLE OF THE SOUTHEAST QUADRANT = 89°31'
1986- WIGHTMAN & ASSOCIATES.-J. KAMER; FOUND CAPPED IRON. WITNESSES: NORTH 48.82' TELEPHONE RISER BOX, WEST 2.0' IRON
ROD IN MON BOX, WEST 21.50' CAPPED IRON

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CAPPED IRON IN PAVEMENT.
THIS CORNER APPROVED BY THE BERRIEN COUNTY REMONUMENTATION PEER GROUP OF SURVEYORS

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3" STEEL PIPE WITH BERRIEN COUNTY BRASS CAP (MARKED 2000 & 35988) IN MON BOX.
THIS POSITION NOT ESTABLISHED BY ORIGINAL GOVERNMENT SURVEYORS. THIS MONUMENT IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE
POSITION OF THE CORNER.

Witnesses:
S03E 24.72' POWER POLE
S02°W 15.85' GUARD RAIL POST
S59°W 30.41' GUARD RAIL POST
S74°W 53.01' GUARD RAIL POST
S81°W 90.65' GUARD RAIL POST
WEST 25.98' SPIKE IN MON BOX
WEST 21.43' J-13, S1/4 CORNER OF SECTION 35
N46°W 57.34' GUARD RAIL POST
N40°W 73.64' 16' HICKORY (DEAD)
N03°W 46.82' TELEPHONE RISER



Signed by Alan K. Bartlett Date 11/02/2000

Surveyor's Michigan License No. 35988
**SURVEY &
REMONUMENTATION**

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN 1983

JAN 31 2001

LIBER 4 , PAGE 244

SECTION