

RATIFIED BY THE BERRIEN COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER MICHIGAN
PUBLIC ACT 345 OF 1990

**Berrien County Remonumentation Program
LAND CORNER RECORDATION CERTIFICATE**

NOV -8 PM 12:51

RECORDED

Alan K. Bartlett
8-22-00
For corners in

Berrien (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>5S</u> R <u>18W</u>	<u>L-1</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

SUNICE TRETHERWAY
REGISTER OF DEEDS
BERRIEN COUNTY, MICHIGAN
11/08/00 111#6048 A66
CORNER \$7.00
11/08/00 111#6048 A66
STATE REMON FEE \$2.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Alan K. Bartlett, in a field survey on March 29, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	15		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- NOT SET BY GLO
- 1972- A. HOWARD; 1/2 MILE DISTANCE WEST (L-1 TO K-1) 2622.20', JOG 13.7' WEST TO L-13
- 1972- A. HOWARD RECORDED SURVEY LIBER 930 PAGE 336, NORTH 1/4 POST (IRON PIPE). WITNESSES: S05°E 31.55' STREET SIGN, WEST 13.70' 3/4" IRON PIPE (S 1/4 POST SEC. 36), N45°W 25.50' NAIL W. SIDE OF POLE; ANGLE OF THE SOUTHWEST QUADRANT 90°30'20"
- 1973- R. GARRETT-LCRC; 1" IRON PIPE. WITNESSES: NORTH 10.78' SOUTH FACE OF LARGE ROCK, S80°W 22.75' STREET SIGN POLE, N45°W 25.57' POWER POLE
- 1981- E.R. STEFAN; IRON PIPE & STONES. WITNESSES: N05°E 8.80' TO FACE OF SIGN POLE, WEST 13.73' SOUTH 1/4 POST, N50°W 24.33' TOP CENTER OF RISER
- 1991- D. PITTS- ABONMARCHE; FOUND IRON PIPE
- 1994- J. KAMER-WIGHTMAN; 1" IRON PIPE. WITNESSES: N35°E 29.00' 6" PEAR (PK), S15°E 47.10' CENTER OF STREET SIGN METAL POST, WEST 13.72' IRON T BAR (S 1/4 COR. SEC 36), N42°W 32.24' RAILROAD TIE POST (PK)
- 1999- D. ZWAR- ABONMARCHE; FOUND 3/4" IRON PIPE 13.73' EAST OF L-13

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" IRON PIPE 2' LONG & 1" STEEL BAR 1.5' LONG ALONGSIDE AND BRICK AROUND THE PIPE. THIS CORNER APPROVED BY THE BERRIEN COUNTY REMONUMENTATION PEER GROUP OF SURVEYORS


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET CONCRETE MONUMENT WITH BRASS CAP (MARKED 2000 & 35988)
MONUMENT IS APPROXIMATELY 10' NORTH OF CENTERLINE OF TOWNLINE ROAD EXTENDED AT THE CENTERLINE OF MERRY STREET EXTENDED NORTH 1' SOUTH OF WOOD FENCE.
THIS POSITION NOT ESTABLISHED BY ORIGINAL GOVERNMENT SURVEYORS. THIS MONUMENT IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.

Witnesses: EAST 38.82' 9" MAPLE
WEST 13.71' L-13 S 1/4 SECTION 36-REMONUMENTED
N25°W 52.61' 9" WALNUT
N43°W 32.14' POST WITH PK NAIL
N53°W 95.04' 36" MAPLE

Signed by Alan K. Bartlett

Date 11/02/00



Surveyor's Michigan License No. 35988

**SURVEY &
REMONUMENTATION**

JAN 31 2001

LIBER 4

PAGE 238

SECTION