

FEB 17 1994

Berrien County Remonumentation

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS
BERRIEN COUNTY MICHIGAN

DEC 3 1 38 PM '93

RECORDED

For corners in

Berrien

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 5S R 19W R-13
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Charles W. Burger, in a field survey on October, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

July 1829 Post set by L. Lyon
Ironwood 5N15W29
Beech 22N41/2E61

(same as NW corner, Section 1-6-19)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

3/4" Iron rod in monument box
PK in Guy Pole S45°E 42.6'
PK in Power Pole S45°W 42.7'
As referenced in recorded survey
L1149 P1315

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" Pipe 36" long with 2 1/2" Remonumentation Brass Cap in Monument Box
End PK in Guy Pole S45°E 42.6'
End PK in Power Pole S45°W 42.7'
Stop Sign N65°E 40.7'
Set PK in Pole N45°W 45.4'

Signed by Charles W. Burger

Date December 3, 1993

Surveyor's Michigan License No. 31589