

RAISED BY THE BERRIEN COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 343 OF 1970

RECORDED

Berrien County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Aug 30 3 39 PM '94

Charles W. Barger
 8-18-94
 For corners in

Charles W. Barger
 REGISTER OF DEEDS
 BERRIEN COUNTY MICHIGAN

_____	Located In:	Corner Code =#
_____ Berrien _____ (County)		
1. Public Land Survey	T <u>5</u> R <u>19</u>	<u>L-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Charles W. Barger, in a field survey on August, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

March 1830 - John Mullett Set Post
 Ash 9 S21E 18
 Elm 9 N62W 14

08/30/94

111W2163 A66
 CORNER \$9.00
 111W2163 A66
 STATE REMON FEE \$2.00

08/30/94

* Additional documentation on Sheet #2.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-9 - 2 1/2" State of Michigan Plaque in Monument Box
 18" Sycamore S38°W 60.3'
 Telephone Pedestal S62°E 75.5'
 Light Pole B297-73 N08°W 29.3'
 Catch Basin S34°W 29.0'

SURVEY & REMONUMENTATION

SEP 15 1994

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-9 - 1" Pipe 13" Long with 2 1/2" Remonumentation Brass Cap in Monument Box
 18" Sycamore S38°W 60.3'
 Telephone Pedestal S62°E 75.5'
 Light Pole B297-73 N08°W 29.3'
 Catch Basin S34°W 29.0'

OVER STONE

And is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by Charles W. Barger P.S.

Date August 29, 1994

Surveyor's Michigan License No. 31589

SOUTH QUARTER CORNER - SECTION 24-5-19
NORTH QUARTER CORNER - SECTION 25-5-19

MARCH, 1830 John Mullett L2. P179. Government Notes
39.92 Set post at average distance for 1/4 Section Corner
Ash 9 S21 E18
Elm 9 N62 W14

AUGUST, 1974 R. Garrett Liber 991, Page 321
Monument Box - 1" I.P. with Plate
Light Pole N. 29.38'
Center of C.B. S. 35 W. 29.35'
8" Oak S. 35 W. 60.30'

OCTOBER, 1982 N. Berndt Liber 1173, Page 1355
Found Government Marker
P.P. N. 05 W. 29.25'
P.P. N. 76 E. 117.0'
6" Dia. Wood fence post South 58.0'

MAY, 1983 R. Harner
2 1/2" Plaque in Monument Box
Center of Power Pole N. 10 W. 29.4'
Telephone Riser S. 56 E. 75.5'
Catch Basin S. 34 W. 29.0'

JUNE, 1983 N. Berndt Liber 1197, Page 1311
Found Government Marker
P.P. N. 05 W. 29.25'
P.P. N. 76 E. 117.0'
6" Dia. Wood fence post South 58.0'

MAY, 1985 R. Harner
Iron in Monument Box
Center of 9" Sycamore S. 34 W. 60.3'
Center of Tel. S. 62 E. 75.5'
Center of Light Pole N. 8 W. 29.5'

MAY, 1994 C. Barger
2 1/2" State of Michigan Plaque in Monument Box
18" Sycamore S. 38 W. 60.3'
Telephone Pedestal S. 62 E. 75.5'
Light Pole B 297-73 N. 08 W. 29.3'
Catch Basin S. 34 W. 29.0'