

**SURVEY & REMONUMENTATION**

12/03/93

111#3386

A33

CORNER

\$7.00

12/03/93

111#3386

A33

STATE REMON FEE \$2.00

FEB 17 1994

*Berrien County Remonumentation*

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

*Charles W. Barger*  
 REGISTER OF DEEDS  
 BERRIEN COUNTY MICHIGAN

DEC 3 1 38 PM '93

RECORDED

For corners in

Berrien  
(County)

Located In:

Corner Code #

- |                                    |   |           |   |            |            |
|------------------------------------|---|-----------|---|------------|------------|
| 1. Public Land Survey              | T | <u>53</u> | R | <u>19W</u> | <u>L13</u> |
|                                    | T | _____     | R | _____      | _____      |
|                                    | T | _____     | R | _____      | _____      |
|                                    | T | _____     | R | _____      | _____      |
| 2. Property Controlling in Section | S | _____     | T | _____      | _____      |
|                                    | S | _____     | T | _____      | _____      |
| 3. Miscellaneous Property in Sec.  | S | _____     | T | _____      | _____      |
|                                    | S | _____     | T | _____      | _____      |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Charles W. Barger, in a field survey on October, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

July, 1829 Post set by L. Lyon  
 Aspen 9N 84W 10  
 DO 9N 44 1/2 E 32  
 (same as N Corner, Section 1-6-19)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

3/4" Iron rod in Monument Box  
 Nail in Power Pole S 45° E 48.00  
 N.W. Corner of CB South 16.45  
 As referenced in Corner recordation  
 L2 P329

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" Pipe 36" long with 2 1/2" Remonumentation Brass Cap in Monument Box  
 Fnd N.W. Corner of CB South 16.45'  
 Fnd Nail in Power Pole S 45° E 48.00'  
 Stop Sign Post N 35° W 37.57'  
 End of Culvert Tube N 45° E 40.75'  
 End of Culvert Tube N 45° W 40.10'  
 Street Sign Post N. 45° W 47.30'

Signed by Charles W. Barger Date December 3, 1993  
 Surveyor's Michigan License No. 31589