

SURVEY & REMONUMENTATION

FEB 17 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE 2/03/93
Filing Requirement of Act 74, Mich. P.A. 1970
 BERRIEN COUNTY REMONUMENTATION 12/03/93

111#3384 AC
 CORNER \$7.0
 111#3384 AC
 STATE REMON FEE \$2.0

For corners in Berrien
 (County)

Located In: Corner Code #

- | | | | | | |
|------------------------------------|---|-----------|---|------------|-----------|
| 1. Public Land Survey | T | <u>5S</u> | R | <u>19W</u> | <u>M6</u> |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

REGISTER OF DEEDS
 BERRIEN COUNTY MICHIGAN
 DEC 3 1 24 PM '93
 RECORDED
 Register of Deeds Stamp File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

I, John G. Kamer, in a field survey on December 2, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-6 J. H. Miller 1873 notes on file at Wightman and Associates, Inc. indicate a set stone at the east 1/4 corner of section 13-5-19 as being 0.17 chains (11.22') south of the west 1/4 corner of section 18. This jog has been referred to since then in old field notes. The only time it was monumented was in 1873, as the stone. The stone seems to have long since disappeared and historically since then, it appears that the well established west 1/4 corner of section 18 has also been used for surveys in section 13. It also appears to have been used in establishing the center of section 13 and other corners on this quarter line since 1894. Also the 1873 Miller notes indicate there may have been a 20' discrepancy running the section line. Based on this evidence, the currently used west 1/4 corner of section 18 is the location of the stone at the east 1/4 corner of section 13 and therefore the west 1/4 corner of section 18 and the east 1/4 corner of section 13 are accepted as the same corner


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-6 Found 3/4" pipe in Mon. Box. Accessories, PK in PP N 20° W 146.30', PK in PP N 20° E 145.80', PK in 8" Apple N 70° E 55.79', PK in PP S 30° W 61.31'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6 Set standard 3' pipe with brass plate in place of 3/4" pipe in Mon. Box. This monument is accepted as a careful and faithful perpetuation of the position of the original corner.

- Set Nail with tag in PP N 13° E 145.90'
- Found Nail w/Tag in PP S 29° W 61.67'
- Set Nail with tag in 8" Twin Apple N 69° E 55.83'
- Set Nail with tag in 24" Stump S 55° E 39.16'



Signed by John G. Kamer Date 12-02-93
 Surveyor's Michigan License No. 27449