

FEB 17 1994

COMMISSION

12/29/93

111W5256 CORNER \$7.00 A66
12/29/93 111W5256 A66
STATE REMON FEE \$2.00

Berrien County Remonumentation Program

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

For corners in

Berrien (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>5S</u> R <u>19W</u>	<u>M-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

DEC 29 3 19 PM '93

Berrien County
REGISTER OF DEEDS
BERRIEN COUNTY MICHIGAN

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Charles W. Barger, in a field survey on December 22, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L.C.R.C. Liber 2, Page 93
Power Pole S50°W 47.8'
Telephone Pole S55°E 66.0'
Light Pole NE 44.5'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found threaded 1/2" iron rod over 1" iron rod in Monument Box
Found PK in Power Pole (B351-104) S50°W 48.55'
Found PK in Telephone Pole (B352-1) S55°E 66.55'
Found PK in Light Pole (B334-36) N41°E 44.75'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed threaded iron rod and replace with 1" iron pipe .80' long with remonumentation 2-1/2" diameter brass cap over 1" iron rod in monument box

Placed "witness point" disc in power pole (B351-104) S50°W 48.64'
Placed "witness point" disc in telephone pole (B352-1) S55°E 66.28'
Placed "witness point" disc in light pole (B334-36) N41°E 44.75'
8" Pine Tree S58°W 74.2'



Signed by Charles W. Barger P.S.

Date December 29, 1993

Surveyor's Michigan License No. 31589