

**SURVEY &
REMONUMENTATION**

APR 26 1995

RECORDED

RATIFIED BY THE BERRIEN COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER MICHIGAN
PUBLIC ACT 345 OF 1990

COMMISSION
BERRIEN COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74; Mich. P.A. 1970

DEC 2 11 11 AM '94

R. L. Harner
11-29-94
For corners in

Bernice Trethewey
REGISTER OF DEEDS
BERRIEN COUNTY MICHIGAN

<u>Berrien</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6 S.</u> , R <u>17 W.</u>	<u>E-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

12/02/94	111#8049	A99
	CORNER	\$7.00
12/02/94	111#8049	A99
	STATE REMON FEE	\$2.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, R.L. Harner, in a field survey on November 30, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-5

Berrien County Road Commission

cap
iron North 33.00'

Wightman and Associates August 28, 1974

plug
24" Beech North 31.81'
utility pole N. 50° W. 42.19'
20" Maple S. 30° W. 37.63'

Wightman and Associates December 3, 1991

plug in mon. box
P.K. nail in power pole N. 45° W. 42.13'
P.K. nail in 36" Maple North 30.22'
P.K. nail in 32" Maple S. 60° W. 65.60'
C/L road South 0.43'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-5

found plug in mon. box over stone

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-5

removed plug and set iron and brass cap in mon. box
iron North 33.40'
P.K. nail in 36" Oak S. 59° W. 65.64'
nail and washer in 36" Oak S. 62° E. 77.15'
P.K. nail in power pole N. 59° W. 42.32'

* Accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by *R. L. Harner* Date 30 NOV 1994

Surveyor's Michigan License No. 22436