

# SURVEY & REMONUMENTATION

RECORDED

APR 26 1995

BERRIEN COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

DEC 2 11 11 AM '94

RAISED BY THE BERRIEN COUNTY  
SURVEY PEER GROUP AS THE  
OFFICIAL CORNER UNDER MICHIGAN  
PUBLIC ACT 345 OF 1990

*[Signature]*  
11-29-94

For corners in

Berrien  
(County)

Located In:

Corner Code #

- |                                       |                               |            |
|---------------------------------------|-------------------------------|------------|
| 1. Public Land Survey                 | T <u>6</u> S., R <u>17</u> W. | <u>F-5</u> |
|                                       | T _____ R _____               | _____      |
|                                       | T _____ R _____               | _____      |
|                                       | T _____ R _____               | _____      |
| 2. Property Controlling in Section    | S _____ T _____ R _____       | _____      |
|                                       | S _____ T _____ R _____       | _____      |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____       | _____      |
|                                       | S _____ T _____ R _____       | _____      |
| 4. Lot No. _____, Recorded Plat _____ |                               |            |
| 5. Private Claims _____               |                               |            |

*[Signature]*  
REGISTER OF DEEDS  
BERRIEN COUNTY MICHIGAN

12/02/94 111#8049 A99  
Register of Deeds Stamp & File Number 7.00  
12/02/94 111#8049 A99

STATE REMON FEE \$2.00

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5					●								
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, R.L. Harner, in a field survey on November 30, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

F-5  
Government - post  
Beech 4" S. 49 1/2° W. 6 links  
Beech 12" N. 2 1/2° E. 30 links  
  
Berrien County Road Commission  
cap  
iron North 33.00'

**Wightman and Associates** August 28, 1974  
plug  
18" Locust N. 50° E. 39.06'  
utility pole S. 55° E. 41.01'  
6" Locust South 25.98'  
**Southwest Survey** October 24, 1975  
mon. box 1' North of C/L road  
nail in W. face of pole S. 65° E. 40.95'  
P.K. nail in E. face of 18" Walnut South 26.18'  
nail in S. face of 15" Walnut N. 80° E. 39.06'  
iron North 33.00'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-5  
found plug in mon. box over stone

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-5  
removed plug and set iron and brass cap in mon. box  
P.K. nail in power pole N. 32° W. 33.93'  
P.K. nail in power pole S. 64° E. 40.94'  
P.K. nail in 6" Maple N. 11° W. 32.33'  
nail in 24" Oak N. 44° E. 38.38'

\*Accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by *[Signature]*  
Surveyor's Michigan License No. 22436

Date 30 Nov 1994

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983