

**SURVEY &
REMONUMENTATION**

APR 26 1995

RECORDED

RATIFIED BY THE BERRIEN COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER MICHIGAN
PUBLIC ACT 345 OF 1990

BERRIEN COUNTY MONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 2 11 11 AM '94

R.L. Harner
11-29-94
For corners in

Bernice Trethewey
REGISTER OF DEEDS
BERRIEN COUNTY MICHIGAN

<u>Berrien</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6 S.</u> , R <u>17 W.</u>	<u>G-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

12/02/94 111#8049 A99
CORNER \$7.00
12/02/94 111#8049 A99
STATE REMON FEE \$2.00
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		

I, R.L. Harner, in a field survey on November 30, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-4

Government - post
Beech 16" N. 64½° W. 9 links
Beech 5" S. 78° E. 21 links

D.M. Dreher August 21, 1973
large stone

corner post East 1.2'
mon. box in pavement N. 89° 54' E. 1318.00'

E.R. Stefan June 12, 1980
stone
center corner post East 1.2'
nail in 4" Cherry N. 70° W. 15.12'
face of 6" tree N. 20° E. 4.5'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-4

found large stone with cross

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-4

set brass cap in large stone
nail and washer in 36" Beech N. 46° W. 51.45'
nail and washer in 36" Sycamore East 101.09'
nail and washer in 10" Maple West 19.31'
nail and washer in 10" Maple N. 85° W. 27.35'

*Accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by *R.L. Harner*

Date 30 Nov 1994

Surveyor's Michigan License No. 22436