

**SURVEY &
REMONUMENTATION**

APR 26 1995

RECORDED

COMMISSION

BERRIEN COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 2 11 11 AM '94

Bernice J. ...
REGISTER OF DEEDS
BERRIEN COUNTY MICHIGAN

RATIFIED BY THE BERRIEN COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER MICHIGAN
PUBLIC ACT 345 OF 1990
R.L. Harner
11-29-94
For corners in

<u>Berrien</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6 S.</u> R <u>17 W.</u>	<u>G-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

12/02/94 111#8049 A99
CORNER \$7.00
12/02/94 111#8049 A99
STATE REMON FEE \$2.00
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, R.L. Harner, in a field survey on November 30, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

<u>G-5</u> Government - post Poplar 30" North 10 links Beech 5" S. 21 2/3° W. 41 links Berrien County Road Commission stone C/L tracks West 2.6' corner post N.E. 38.7' T-rail S.E. 68.7' T-rail S.W. 67.2' U.S. B.M. S.W. 89.8'	E.R. STEFAN June 9, 1981 R.R. spike East 5.0' U.S.G.S. cap S. 30° W. 90.0' face conc. post N. 60° E. 38.8' Peirce and Associates 1993 set R.R. spike from existing witnesses center T-rail (buried) S. 60° W. 67.17' center T-rail (buried) S. 60° E. 68.70' nail in power pole N. 60° W. 46.50' U.S.G.S. B.M. S. 30° W. 89.80'
--	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-5
found railroad spike

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-5
set brass cap in mon. box (cap in conc.)
center of T-rail S. 60° W. 67.17'
center of T-rail S. 60° E. 68.70'
nail in power pole N. 60° W. 46.50'
center of U.S.G.S. B.M. S. 30° W. 89.80'

*Accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by *R.L. Harner* Date 30 Nov 1994
Surveyor's Michigan License No. 22436