

RECORDED

ATIFIED BY THE BERRIEN COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990

BERRIEN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

98 NOV 19 PM 4:47

BERNICE TRETHERWAY REGISTER OF DEEDS BERRIEN COUNTY, MICHIGAN

10-06-98

Form with fields: For corners in BERRIEN COUNTY, Located in: BERRIEN TWP., Corner Code # (M-4) E 1/4 POST SEC 12. Includes sections for Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., and Private Claims.

Register of Deeds Stamp & File Number

11/17/98 111#6180 A77 CORNER \$7.00 11/19/98 111#6180 A77 STATE REMON. FEE \$2.00

Grid table with columns A-L and rows 2-13. Contains numbers 1-38 in a specific layout.

I, Alan Bartlett in a field survey on November 13 1998 hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

March 1827 GLO William Brookfield Book 1, Page 152 of field notes. North on East side of Sec 12 40.00 1/2 Mile Post witnesses W. Oak 26 N24 1/2 W 21lks "do" 10 S31 1/2 W 16lks

SURVEY & REMONUMENTATION

JAN 12 1999

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Reestablished corner using 1/2 way point between existing Berrien County Monuments. This Government Monument was restored with the approval of the Berrien County Remonumentation Peer Group of Surveyors on October 6 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Concrete Monument with Berrien County Remonumentation cap 1.7' East of a North-South Fence Line and 7' North of East-West Fence at 1/2 way point between existing Berrien County Monuments.

witnesses N25E Set Nail and Flasher S.E. side of 30" Oak 37.81' N72E Set Nail and Flasher N.W. side of 8" Hickory 9.58' S70E Set Nail and Flasher N. side of 18" Poplar 22.59' S20E Set Nail and Flasher E side of 22" Tree 8.88'

Corner is accepted as a careful and faithful reestablishment of the position of the original corner

Signed by Alan K. Bartlett Date 11/16/98 Surveyor's Michigan License No. 35988

