

RAJIFIED BY THE BERRIEN COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

BERRIEN COUNTY REMONUMENTATION

[Signature]
7-06-94

REGISTER OF DEEDS BERRIEN COUNTY MICHIGAN

AUG 30 3 47 PM '94

RECORDED

FOR CORNERS OF	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>6</u> N. S., R. <u>17</u> E. W.		M-5
2. PROPERTY CONTROLLING IN SECTION <u>13</u> , T. <u>6</u> N. S., R. <u>17</u> E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

08/30/94 111#2168 A99
CORNER \$7.00
08/30/94 111#2168 A99
STATE REMON FEE \$2.00
REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Robert W. Prestine, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June, 1994, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

M-5
NE cor. Sec 13
Set post Wm. Brookfield D.S. March 1827
Govt. Pepperage 12" North 3 lks.
Tamarak 10" S 47° W 66 lks.

SURVEY & REMONUMENTATION
SEP 15 1994
COMMISSION

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

M-5
Found stone. Orig. fd. stone in 1959 ± while employed by H. L. Dreher, R.L.S. (no record)
Used by R. L. Harner-Barger Eng. May 1978
Shows cor. North of NW cor. Sec. 18-6-16
Govt. maps show cor to be South of NW cor Sec. 18-6-16
Cass Co. Govt. notes - 50 lks. South & Berrien Co. Govt. notes - 50 lks North.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-5
Removed stone & set Berrien Co. conc. monument with remonumentation cap.
Center line 17" Maple S 21° W 14.22' Nail & washer in E. side.
Center line 13" Hickory S 10° W 33.05' Nail & washer in S. side.
Center line 24" Pepperage North 2.85' Nail & washer in E. side.
Cass Co. conc. monument South 33.20'

SIGNED BY Robert W. Prestine DATE August 27, 1994

SURVEYOR'S MICHIGAN REGISTRATION NO. 18662

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



LIBER 3 PAGE 122

SURVEYOR'S MICHIGAN REGISTRATION NO. _____