

RATIFIED BY THE BERRIEN COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 343 OF 1990

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

BERRIEN COUNTY REMONUMENTATION

Robert W. Prestine
7-06-94

FOR CORNERS OF	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>6</u> ^{N.} S., R. <u>17</u> ^{E.} W. _____		M-8
2. PROPERTY CONTROLLING IN SECTION <u>24</u> , T. <u>6</u> ^{N.} S., R. <u>17</u> ^{E.} W. _____		
3. MISCELLANEOUS PROPERTY IN SECTION _____ , T. _____ N. S., R. _____ E. W. _____		

REGISTER OF DEEDS
 BERRIEN COUNTY MICHIGAN
Robert W. Prestine

RECORDED
 AUG 30 3 47 PM '94

4. LOT NO. _____ , RECORDED PLAT _____	08/30/94	111#2168	A99
5. PRIVATE CLAIMS _____	08/30/94	111#2168	A99

REGISTER OF DEEDS STAMP AND FILING NUMBER FEE \$2.00

I, Robert W. Prestine, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June, 1994, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

SURVEY & REMONUMENTATION
 SEP 15 1994
 COMMISSION

M-8
 E 1/4 cor. Sec. 24
 Set post Wm. Brookfield D.S. March 1827
 W. Oak 26" on 1/4 cor.
 No other wits.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

M-8
 Set corner at Govt. prorated jog from corners in Sec. 19-6-16 12.54' South of West 1/4 cor. Sec. 19-6-16

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-8
 Set 3/4" x 18" iron with Berrien County Remonumentation Cap on NE side of Conc. pillar and poured conc. monument in place.
 Center line 9" Oak S 78° W 11.1' Nail & washer in N. side.
 Face of 34" Ash W. 37.55' Nail & washer in face.
 26" Maple N 45° E 1.95' Nail & washer in W. side.
 15" Cherry N 47.19' Nail & washer in E. side.


SIGNED BY Robert W. Prestine DATE August 27, 1994

SURVEYOR'S MICHIGAN REGISTRATION NO. 18662

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
 CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
 MICHIGAN REGISTERED LAND SURVEYOR



LIBER 3 PAGE 118

SURVEYOR'S MICHIGAN REGISTRATION NO. _____