

RATIFIED BY THE BERRIEN COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 315 OF 1990

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
BERRIEN COUNTY REMONUMENTATION

Robert W. Prestine
7-06-94

REGISTER OF DEEDS
 BERRIEN COUNTY MICHIGAN
Robert W. Prestine

AUG 30 3 47 PM '94

RECORDED

FOR CORNERS OF	County	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	Berrien	T. 6 N. S., R. 17 W.	M-9
2. PROPERTY CONTROLLING IN SECTION	25	T. 6 N. S., R. 17 W.	
3. MISCELLANEOUS PROPERTY IN SECTION		T. N. S., R. E. W.	
4. LOT NO.		RECORDED PLAT	08/30/94
5. PRIVATE CLAIMS			08/30/94

111#2168 A99
 CORNER \$7.00
 111#2168 A99
 REGISTER OF DEEDS STATE OF MICHIGAN AND \$2.00
 FILING NUMBER

I, Robert W. Prestine, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June, 1994, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
M-9

SURVEY & REMONUMENTATION
 SEP 15 1994
COMMISSION

NE. cor. Sec. 25
 Set post Wm. Brookfield D.S. March 1827
 W. Ash 6" S 44½° W 41 lks.
 Maple 7" N 39½° W 23 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
M-9

Found Berrien County Road Commission in mon. box
 Wit's. all o.k.
 1" iron North 5.0'
 1" iron North 38.0'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-9

Removed Berrien County mon. and set 3/4" x 36" pipe with Berrien County remonumentation cap and set new mon. box inside old mon. box and raised.

1" iron North 37.75'
 19" Maple N 38° W 42.25' Nail & washer in NW. side
 23" Maple S 59° W 60.65' Nail & washer in SW. side
 1" iron North 5.0'
 Cass County corner South 16.96'


SIGNED BY *Robert W. Prestine* DATE August 27, 1994

SURVEYOR'S MICHIGAN REGISTRATION NO. 18662

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



LIBER 3 PAGE 117

SURVEYOR'S MICHIGAN REGISTRATION NO. _____