

RATIFIED BY THE BERRIEN COUNTY, SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER PUBLIC ACT 345 OF 1990

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Robert W. Prestine
7-06-94

BERRIEN COUNTY REMONUMENTATION

FOR CORNERS OF -	LOCATED IN -	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>6</u> N. S., R. <u>17</u> E. W.		M-12
2. PROPERTY CONTROLLING IN SECTION <u>36</u> , T. <u>6</u> N. S., R. <u>17</u> E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		08/30/94
5. PRIVATE CLAIMS _____		08/30/94

REGISTER OF DEEDS
BERRIEN COUNTY MICHIGAN

Aug 30 3 47 PM '94

RECORDED

111#2168 APP
CORNER \$7.00
111#2168 APP
REGISTER OF DEEDS STAMP AND FILING NUMBER FEE \$2.00

I, Robert W. Prestine, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June, 1994, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

M-12

East 1/4 cor. Sec. 36

Set post Wm. Brookfield D.S. March 1827
Beech 9" S 50° W 27 lks.
Beech 20" N 20° W 36 lks.

SURVEY & REMONUMENTATION

SEP 15 1994

COMMISSION

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

M-12

Found 1" iron in mon. box set by Berrien County Road Commission

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-12

Removed 1" iron and set 3/4" x 36" pipe with Berrien County remonumentation cap and raised mon. box.

37" Maple N 67° W 146.77' Nail & washer in NE. side
10" Maple S 44° W 28.37' Nail & washer in NW. side
8" Maple S 38° E 35.95' Nail & washer in NW. side
Cass County cor. South 7.12'

SIGNED BY *Robert W. Prestine* DATE August 27, 1994


SURVEYOR'S MICHIGAN REGISTRATION NO. 18662 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. _____



LIBER 3 PAGE 114