

RATIFIED BY THE BERRIEN COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990

RECORDED

BERRIEN COUNTY REMONUMENTATION  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

97 OCT 31 PM 2:04

BERNICE TRETHERWAY  
 REGISTER OF DEEDS  
 BERRIEN COUNTY, MICHIGAN

*Charles W. Barger*  
 10-23-97

For corners in

BERRIEN  
 (County)

Located In:

Corner Code #

- |                                    |   |          |   |           |      |
|------------------------------------|---|----------|---|-----------|------|
| 1. Public Land Survey              | T | <u>6</u> | R | <u>19</u> | E-13 |
|                                    | T |          | R |           |      |
|                                    | T |          | R |           |      |
|                                    | T |          | R |           |      |
| 2. Property Controlling in Section | S |          | T |           | R    |
|                                    | S |          | T |           | R    |
| 3. Miscellaneous Property in Sec.  | S |          | T |           | R    |
|                                    | S |          | T |           | R    |

10/31/97 111#2484 A99  
 CORNER \$9.00  
 10/31/97 111#2484 A99  
 Register of Deeds Stamp & File Number 2.00

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, CHARLES W. BARGER, in a field survey on OCTOBER, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

L. LYON SET POST TO SECS 32 & 33  
 FEB 1830 BEECH 11 N40W 9  
 SUGAR 11 N

Surveyor's  
**REMONUMENTATION**

NOV 21 1997

COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C. BARGER FOUND RR SPIKE  
 1997  
 NW COR SEC 4-17-19 E. 81.65'  
 P.K. IN PP S70DEG45'E 110.3'  
 P.K. IN PP N54DEG34'W 49.31'  
 P.K. IN PP N81DEGE 187.26'  
 NE COR I-BEAM 8TH FENCE POST FROM E END  
 S25DEGW 38.11'  
 NW COR I-BEAM 4TH FENCE POST FROM E END  
 S25DEGE 38.75'  
 WITNESS CORNER 1/2" REBAR IN MON BOX S65DEGW 5.74'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13 1" PIPE 36" LONG WITH 2 1/2" REMONUMENTATION BRASS CAP IN MONUMENT BOX  
 2 1/2" REMONUMENT MARKER OVER 1" PIPE E 81.65'  
 WITNESS TAG IN PP S70DEG45'E 110.3'  
 WITNESS TAG IN PP N54DEG34'W 49.31'  
 WITNESS CORNER 1/2" REBAR IN MONUMENT BOX S65DEGW 5.74'  
 NE COR I-BEAM 8TH FENCE POST FROM E END S25DEGW 38.11'  
 NW COR I-BEAM 4TH FENCE POST FROM E END S25DEGE 38.75'



AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Charles W. Barger Date OCTOBER 31, 1997

Surveyor's Michigan License No. 31589

BARGER ENGINEERING, INC.  
BERRIEN COUNTY REMONUMENTATION

SOUTHEAST CORNER SECTION 32, TOWNSHIP 6 SOUTH, RANGE 19 WEST  
(BROWNTOWN & PARDEE)

(E-13)

L. Lyon  
Feb 1830

Set Post to Secs 32 & 33  
Beech 11 N40W 9  
Sugar 11 N

Berrien County  
Road Commission  
1925-40

81.7' W. of NW Cor Sec 4-7-19  
End Post W. Side of Lane 20.3'  
12" Elm NW 32.0'  
Stone 8" Tele Pole SW 40.9'

R. Harner  
1984

Found 3"  
P.K. in PP N 5deg E 59.43'  
NE Cor I Beam Fence Pst S25degW 38.26'  
NW Cor I Beam Fence Pst S25degE 38.78'  
3" Iron East 82.08'

C. Barger  
1997

Found RR Spike  
NW Cor Sec 4-17-19 E. 81.65'  
P.K. in PP S70deg45'E 110.3'  
P.K. in PP N54deg34'W 49.31'  
FOUND WITNESS CORNER 1/2" REBAR IN MON BOX S65DEGW 5.74'  
NE Cor I-Beam 8th Fence Pst From  
E end S25degW 38.11'  
NW Cor I-Beam 4th Fence Pst From  
E end S25degE 38.75'

Survey &  
REMONUMENTATION

NOV 21 1997

COMMISSION

JOB ASSIGNMENT 1996-02-0250

LIBER

4 PAGE

12