

RAISED BY THE BERRIEN COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990

RECORDED

BERRIEN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

97 OCT 31 PM 2:04

BERNICE TRETHERWAY
 REGISTER OF DEEDS
 BERRIEN COUNTY, MICHIGAN

For Corners in BERRIEN
 (County)

Located In: _____ Corner Code # _____

- 1. Public Land Survey T 6 R 19 G-13
 Common to: T75, R19W, G-1
 T ~~7~~ R ~~19~~
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

10/31/97 111#2484 A99
 CORNER \$9.00
 Register of Deeds Stamp & File Number A99
 STATE REMON FEE \$2.00

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, CHARLES W. BARGER, in a field survey on OCTOBER, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L. LYON SET POST
 1830 ASPEN 8 N58W 40
 ASPEN 5 N70E 54

BORDER
 REMONUMENTATION

NOV 21 1997

COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C. BARGER FOUND RR SPIKE
 1997 P.K. IN TELE POLE S71DEG19'E 75.83'
 HYDRANT N19DEG24'W 53.72'
 P.K. IN PP S34DEG02'W 26.98'
 NE COR HDWL S21DEG19'W 8.21'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13 & G-1 1" PIPE 36" LONG WITH 2½" REMONUMENTATION BRASS CAP IN MONUMENT BOX
 WITNESS TAG IN TELE POLE S71DEG19'E 75.83'
 HYDRANT N19DEG24'W 53.72'
 WITNESS TAG IN PP S34DEG02'W 26.98'
 NE COR HDWL S21DEG19'W 8.21'

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.



Signed by Charles W. Barger

Date OCTOBER 31, 1997

Surveyor's Michigan License No. 31589

BARGER ENGINEERING, INC.
BERRIEN COUNTY REMONUMENTATION

SOUTHWEST CORNER SECTION 34, TOWNSHIP 6 SOUTH, RANGE 19 WEST (G-13)
NORTHWEST CORNER SECTION 3, TOWNSHIP 7 SOUTH, RANGE 19 WEST (G-1)

HOLDEN ROAD & BROWNTOWN

L. Lyon
1830

Set Post
Aspen 8 N58W 40
Aspen 5 N70E 54

Berrien County
Road Commission
1940-1959

40' W of +1's of W. Pst of S. Rail of Bridge
Cor Fence Pst NW 38.2'
Cor Fence Pst S 14.2'
4" Ash N70degW 43.7'

J. Kamer
1989

P.K. Nail in Road
NE Cor Hdwl S10degW 9.3'
SE Cor Hdwl N10degW 25.53'
P.K. in Wood Pst S20degW 26.95'
Centerline Browntown Road N 6.4'

C. Barger
1997

Found RR Spike
P.K. in Tele Pole S71deg19'E 75.83'
Hydt N19deg24'W 53.72'
P.K. in PP S34deg02'W 26.98'
NE Cor Hdwl S21deg19'W 8.21'

SURVEY &
REMONUMENTATION

NOV 21 1997

COMMISSION

JOB ASSIGNMENTS 1997-02-0297
1997-02-0298