

RATIFIED BY THE BERRIEN COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1890

09/02/94 111#2445 H33
 09/02/94 CORNER \$9.00
 111#2445 A33
 STATE REMON FEE \$2.00

BERRIEN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

John G. Kamer
 8-18-94
 For corners in

Berrien
 (County)

Located In: Corner Code #/

- 1. Public Land Survey T 6S R 19W I-4
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

REGISTERED LAND SURVEYOR
 JOHN G. KAMER
 BERRIEN COUNTY MICHIGAN
 SEP 2 4 21 PM '94
 RECORDED

Register of Deeds Stamp & File Number

I, John G. Kamer, in a field survey on August 24, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 (See Back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found P.K. nails and witness ties.
 The perpetuation of the corner as evidenced by the history of witness ties appears reliable and accurate.

SURVEY &
 REMONUMENTATION
 NOV 07 1994
 COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 I-4
 Set standard 3'x1" pipe w/brass plate in set mon. box in place of 6" deep PK that was 0.21' North of a PK on road surface set in 1984. Corner is accepted as a careful and faithful perpetuation of the original corner.
 Set 8 penny nail w/tag in wood guard post S49°W 23.25'
 Set 8 penny nail w/tag in wood guard post N72°E 20.20'
 Set 8 penny nail w/tag in wood guard post S81°W 17.51'
 Set 8 penny nail w/tag in P. Pole S58°E 32.95'



Signed by *John G. Kamer* Date 9-01-94
 Surveyor's Michigan License No. 27449

1830

Lucius Lyon
40.00 Set Post Com to Secs 10 & 11-6-19
Sycamore 40 S 77 W 10
Lynn 7 S 84 E 7

1945

J.H. Dewey
Fnd. Stone

1948-1965

BCRC
Stone

May 4, 1970

W & A
PK

Sept. 23, 1976

M.R. Rushlow (W & A)
Fnd. I.P.

May 10, 1984

J. G. Kamer L 1213 P1212
Set PK Nail from 1976 Survey Notes
(Cor. out from Constr.)
PK Nail in Guard Post
N 75° E 20.12'
PK Nail in Guard Post
S 45° W 23.08'
PK Nail in Power Pole
S 60° E 32.90'

Jan. 2, 1987

J. G. Kamer
W 1/4 Cor., 11-6-19
Set PK Nail (Really found 1984 nail)
PK Nail in Guard Post
N 75° E 20.12
PK Nai in Guard Post
S 45° W 23.08'
PK Nail in Power Pole
S 60° E 32.90'

June 12, 1991

J. G. Kamer
W 1/4 Cor. Fnd. P.K. Nail
P.K. in Guard Post N 75° E 20.12'
P.K. in Guard Post S 45° W 23.08'
P.K. in P.P. S 60° E 32.90'

December 27, 1991

J.G. Kamer
W 1/4 Cor. PK in CL Road
PK in Guard Post N 75° E 20.12'
PK in Guard Post S 45° W 23.08'
PK in PP S 60° E 32.90'

August 11, 1994

J. G. Kamer
Found PK in CL Road
PK in Guard Post N 75° E 20.12'
PK in Guard Post S 45° W 23.08'
PK in PP S 60° E 32.90'