

SURVEY & REMONUMENTATION

FEB 17 1994

COMMISSION

12/03/93

12/03/93

111#3386 A33  
CORNER \$7.00  
111#3386 A33  
STATE REMON FEE \$2.00

Berrien County Remonumentation

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS  
BERRIEN COUNTY MICHIGAN

DEC 3 1 38 PM '93

RECORDED

For corners in

Berrien  
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 6S R 19W K-1  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Charles W. Barger, in a field survey on October, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

July, 1829 Post set by L. Lyon  
Ironwood S N 15 W 29  
Beech 22 N 4 1/2 E 61

(Same description as SW Corner, Section 36-5-19)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

3/4" Iron rod in Monument Box  
PK in Guy Pole S 45° E 42.6'  
PK in Power Pole S 45° W 42.7'  
As referenced in recorded survey  
L149 P1315

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K1  
1" Pipe in 36" long with 2 1/2" Remonumentation Brass Cap in Monument Box  
Fnd PK in Guy Pole S 45° E 42.6'  
Fnd PK in Power Pole S 45° W 42.7'  
Stop Sign N 65° E 40.7'  
Set PK in Pole N 45° W 45.4'

Signed by Charles W. Barger  
Surveyor's Michigan License No. 31589

Date December 3, 1993