

FEB 17 1994

Berrien County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS
BERRIEN COUNTY MICHIGAN

DEC 3 1 38 PM '93

RECORDED

For corners in

Berrien
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 65 R 19W L-1
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Sec. S T R
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Register of Deeds Stamp & File Number

I, Charles W. Banger, in a field survey on October, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

July, 1829 Post set by L. Lyon
Aspen 9N84W10
DO 9N 44 1/2 E 32

(same as S. corner, Section 36-5-19)


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

3/4" Iron Rod in monument box
Nail in Power Pole S45°E 48.00
N.W. corner of CB South 16.45
As referenced in Corner Recordation

L2 P329

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-1
1" pipe 36" long with 2 1/2" Remonumentation Brass Cap in Monument Box
End NW corner of CB South 16.45'
End Nail in Power Pole S45°E 48.00'
Stop Sign Post N35°W 37.57'
End of Culvert Tube N45°E 40.75'
End of Culvert Tube N45°W 40.10'
Street Sign Post N45°W 47.30'



Signed by Charles W. Banger

Date December 3, 1993

Surveyor's Michigan License No. 31589