



SOUTHEAST CORNER - SECTION 36-6-19  
NORTH EAST CORNER SECTION 1-7-  
SOUTHWEST CORNER SECTION 31-6-18  
NORTHWEST CORNER - SECTION 6-7-18 (A-1)

JULY. 1828

William Brookfield L2. P3 Government Notes

60.00 Set frost corner to Townships 6 & 7 South. Ranges 18  
& 19 West

Lynn 20 S. 75 E. 37  
Sugar 20 N. 10 1/2 E. 60

1829

Lucius Lyon L2. P62 Government Notes

90.00 Set frost corner to Townships 6 & 7 South. Ranges 18  
& 19 West

Lynn 20 S. 75 E. 37  
Sugar 20 N. 10 1/2 E. 60

Circa 1945

Berrien County Road Commission

R.R. Spike  
Cor. Grade Post SE 35.4'  
Iron Pipe & Fence West 33' on line  
Cor. Cherry SE 46.3'  
Cherry Row East is South 34.0  
Cherry Row South is East 31.5'  
Cor. Headwall SE 24.4'  
Cor. Headwall NE 29.6'

Feb. 1951

H.L. Dreher

R.R. Spike

JAN. 1983

J. Kamer L. 1181. P. 1260 Recorded Survey

Found 3/4" Iron  
PK in Cor. Fence Post S. 88 W. 24.32'  
PK in Tele. Buried Cable Post S. 40 E. 64.35'  
PK in Guard Post N. 20 W. 65.79'

NOV. 1994

C.W. Barber

Found 3/4" Iron Rod  
Set Nail & Witness Tag in base of Cherry Tree S. 89 W 62.4'  
Set Nail & Witness Tag in PP by Tele. Riser S. 57 E. 52.5  
Set Nail & Witness Tag in Tele. Buried Cable Post (4x4)  
N. 21 E. 70.0'  
Found 3/4" Iron Pipe West 33.0 (1.3' deep)

SURVEY &  
RECORDS SECTION

DEC 7 1995

COMMISSION