

RATIFIED BY THE BERRIEN COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990

RECORDED

BERRIEN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

OCT 27 PM 1:07

for corners in Berrien (County) Located in: _____ Corner Code # _____
 4-21-98

BERNICE TRETHERWAY
 REGISTER OF DEEDS
 BERRIEN COUNTY, MICHIGAN

- 1. Public Land Survey T 7S R 17W _____ M-2
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____
- 3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____

10/27/98 111#4092 A44
 Register of Deeds Stamp & File Number #7.00
 10/27/98 111#4092 A44
 STATE REMON FEE \$2.00

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

V. J. Strebs, in a field survey on May 13, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1. Description of original monument and accessories and/or subsequent restoration:

- 1827 WILLIAM BROOKFIELD, D.S. - NORTH ON EAST SIDE OF SECTION 1, MEASURED 40 CHAINS, SET POST; 6" ELM S70½°W 35 LINKS; 18" WHITE OAK N4°W 54 LINKS.
- MAY 22, 1978 R.W. PRESTINE, SET 2½" X 50" PIPE W/ ½" IRON PIPE INSIDE CAP #18662; FACE 30° WHITE WOOD N47°E 205.00; FACE 24° BEECH S83°E 181.81; FACE 20° BEECH N71°E 174.25'.
- DEC. 28, 1995 R.W. PRESTINE; FOUND ½" IRON INSIDE OF 2½" IRON PIPE 21.2' NORTH OF CASS COUNTY REMONUMENTATION MONUMENT.

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND ½" IRON PIPE (CAP #18662) INSIDE OF 2½" IRON PIPE.

SURVEY & REMONUMENTATION

NOV 20 1998

SECTION

3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 4" X 3 FT CONCRETE MONUMENT W/B.C.R.P. BRASS CAP; WIT TAG IN 12" ELM N55°W 111.94'; WIT TAG IN 18" BEECH S80°E 181.34'; WIT TAG IN 20" BEECH N70°E 174.28'; CASS COUNTY REMONUMENTATION MONUMENT SOUTH 21.16'.

ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by [Signature]
 Surveyor's Michigan License No. 26469



Date 7-9-98