

RECORDED

RATIFIED BY THE BERRIEN COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990

BERRIEN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

98 OCT 27 PM 1:07

BERNICE TRETHERWAY REGISTER OF DEEDS BERRIEN COUNTY, MICHIGAN

For corners in 4-21-98

Berrien (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7S</u> R <u>R17W</u>	<u>M-3</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

10/27/98 111#4092 A44  
 CORNER \$7.00  
 10/27/98 111#4092 A44  
 Register of Deeds Stamp & File Number  
 STATE REMON FILE \$2.00

I, V. J. Strebs, in a field survey on May 13, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1827 WILLIAM BROOKFIELD, D.S. - NORTH ON EAST SIDE OF SECTION 12, MEASURED 80 CHAINS, SET POST FOR CORNER OF SECTIONS 1 & 12; 15" BEECH S14°W 27 LINKS; 8" SUGAR N41½°W 33 LINKS.  
 MAY 1978 R.W. PRESTINE, IRON (NO WITNESSES)  
 DEC. 28, 1995 R.W. PRESTINE; FOUND ½" IRON 25.74' NORTH OF CASS COUNTY REMONUMENTATION MONUMENT.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(FOUND ½" IRON)

SURVEY & REMONUMENTATION

NOV 20 1998

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 4" X 3 FT CONCRETE MONUMENT W/B.C.R.P. BRASS CAP; WIT TAG IN 12" TRIPLE ASH S60°E 26.55'; WIT TAG IN 15" SYCAMORE S50°W 35.32'; WIT TAG IN 15" SYCAMORE S25°W 65.38'; CASS COUNTY REMONUMENTATION MONUMENT SOUTH 25.83'.  
 ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by [Signature]  
 Surveyor's Michigan License No. 26469



Date 7-9-98