

RECORDED

ATTESTED BY THE BERRIEN COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990

BERRIEN COUNTY REMONUMENTATION 98 OCT 27 PM 1:07 LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

BERNICE TRETHERWAY REGISTER OF DEEDS BERRIEN COUNTY, MICHIGAN

Signature of V.J. Strebs and date A-21-98

Form with fields: Berrien (County), Located In, Corner Code #, 1. Public Land Survey, 2. Property Controlling in Section, 3. Miscellaneous Property in Sec., 4. Lot No., 5. Private Claims

10/27/98 111#4092 A44 Register of Deeds Stamp & File Number \$7.00 STATE REMON FEE \$2.00

Grid table with columns A-M and rows 1-13, containing numbers 1-36.

I, V. J. Strebs, in a field survey on May 13, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1827 WILLIAM BROOKFIELD, D.S. - NORTH ON EAST SIDE OF SECTION 12, MEASURED 40 CHAINS, SET POST; 26" BEECH S13 1/2° W 17 LINKS
1960's DM DREHER - PLAT OF "MISTY ACRES" SET CONCRETE MONUMENT

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CONCRETE MONUMENT

SURVEY & REMONUMENTATION

NOV 20 1998

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 4" X 3 FT CONCRETE MONUMENT W/B.C.R.P. BRASS CAP; WIT TAG IN 8" MAPLE N10°E 65.64'; S.W. COR. BRICK HOUSE N20°E 76.26'; S.W. COR. FRAME SHED S45°E 5.58'; CASS COUNTY REMONUMENTATION MONUMENT SOUTH 7.65'.

ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by [Signature] Surveyor's Michigan License No. 26469



Date 7-9-98

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971 REVISED MAY 14, 1975 REVISED JAN., 1983 REVISED OCT., 1995