

APPROVED BY THE BERRIEN COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1930

*W. W. Barger*  
 December 17, 1994  
 For corners in

Berrien County Remonumentation  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS  
 BERRIEN COUNTY MICHIGAN  
*B. W. Barger*

DEC 16 4 02 PM '94

RECORDED

Berrien (County)	Located In:	Corner Code #
1. Public Land Survey	T 8 R 18	A-1
Common to: T7S, R18W, A13	T R	
T7S, R19W, M13	T R	A-13
T8S, R19W, M1	T R	
2. Property Controlling in Section	S T R	
3. Miscellaneous Property in Sec.	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Charles W. Barger, in a field survey on November, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:


1829 Lucius Lyon  
 80.00 Set frost corner to Townships 7 & 8 South, Ranges 18 & 19 West  
 Beech 14 N. 68 W. 24.  
 Ash 14 S. 21 E. 41

12/16/94 111#9004 A66  
 CORNER \$9.00  
 12/16/94 111#9004 A66  
 STATE REMON FEE \$2.00

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-1 Found 1/2" iron in Monument Box  
 Face of Guy Pole N.40W., 39.3'  
 Face of Power Pole N.37E., 36.7'  
 Face of Guy Pole S.37E., 31.7'  
 Found Nail in 12" Walnut N.40E., 62.4'

SURVEY & RECORD  
 DEC 17 1994



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-1 Set 1" pipe (2' long) with 2 1/2" Brass Remonumentation Cap over 1/2" iron in Monument Box  
 Set Witness Tag on Guy Pole N.40W., 39.3'  
 Set Witness Tag on Power Pole N.37E., 36.7'  
 Set Witness Tag on Guy Pole S.37E., 31.7'  
 Set Witness Tag in 12" Walnut N.40E., 62.4'

And is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by Charles W. Barger  
 Surveyor's Michigan License No. 31589

Date December 16, 1994

SOUTHEAST CORNER - SECTION 36-7-19  
NORTHEAST CORNER - SECTION 1-8-19  
SOUTHWEST CORNER - SECTION 31-7-18  
NORTHWEST CORNER - SECTION 6-8-18 (A-1)

10

1829 Lucius Lyon L2. P65 Government Notes

80.00 Set frost corner to Townships 7 & 8 South, Ranges 18 & 19 West

Beech 14 N. 68 W. 24  
Ash 14 S. 21 E. 41

Circa 1945 Berrien County Road Commission

T-Rail  
Elec. Pole NE 36.2  
Elec Guv Pole NW 38.5'  
Elec Guv Pole SE 31.5'  
6" Walnut N 30 E 72.8'  
NE Cor Conc hdwall SW 33.2'  
NW Cor Conc hdwall S 10 E 26.0'

JUNE, 1972 E.R. Stefan L935. P687 Recorded Survey

Monument Box  
Face PP N. 45 W. 39.0'  
Face PP N. 45 E. 36.4'  
Face PP S. 45 W. 31.4'

NOV 28, 1994 C.W. Barger

1/2" Iron in Monument Box  
Face of Guv Pole N. 40 W. 39.0'  
Face of Power Pole N. 37 E. 36.4'  
Face of Guv Pole S. 37 E. 31.4'  
Found Nail in 12" Walnut N. 40 E. 62.4'

QUAMEY &  
SURVEYING & MAPPING

DEC 17 1995

COMMISSION