

ATTIFIED BY THE BERRIEN COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990

RECORDED

BERRIEN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

97 OCT 31 PM 2:04

BERNICE TRETHERWAY REGISTER OF DEEDS BERRIEN COUNTY, MICHIGAN

[Signature]
10-23-97
For corners in BERRIEN (County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>7</u> R <u>19</u>	F-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

10/31/97 111W2484 A99
CORNER \$9.00
10/31/97 111W2484 A99
Register of Deeds Stamp & File Number \$2.00

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, CHARLES W. BARGER in a field survey on OCTOBER, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

L. LYON
1830

Surveyor
REMONUMENTATION

NOV 2 1 1997

COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C. BARGER 1997
5/8" REBAR IN MONUMENT BOX
SAN MH N83DEG20'W 54.44'
WATER MH N17DEG29'W 48.4'
P.K. IN PP S60DEG27'E 57.27'
5/8" REBAR IN MON W 40.88'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-1 1" PIPE 36" LONG WITH 2 1/2" REMONUMENTATION BRASS CAP IN MONUMENT BOX
SAN MANHOLE N83DEG20'W 54.44'
WATER MANHOLE N17DEG29'W 48.4'
WITNESS TAG IN PP S60DEG27'E 57.27'
2 1/2" REMONMENT MARKER OVER 1" PIPE W 40.88'

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.



Signed by Charles W. Barger Date OCTOBER 31, 1997

Surveyor's Michigan License No. 31589

LIBER 4 PAGE 7

BARGER ENGINEERING, INC.
BERRIEN COUNTY REMONUMENTATION

NORTH QUARTER POST SECTION 4, TOWNSHIP 7 SOUTH, RANGE 19 WEST
(F-1)
DATE ROAD

L. Lyon
1830

Berrien County
Road Commission
1920-45

Stone & Plow Point
30" Maple S 35.2'
12" Hickory N15degE 36.3'
30" Oak N20degw 74.0'
Fence S 23.7'

C. Barger
1997

5/8" Rebar in Monument Box
San MH N83deg20'W 54.44'
Water MH N17deg29'W 48.4'
P.K. in PP S60deg27'E 57.27'
5/8" Rebar in Mon W 40.88'

Berrien County
REMONUMENTATION

NOV 21 1997

COMMISSION

JOB ASSIGNMENT 1997-02-0294