

CONFIRMED BY THE BERRIEN COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990

Berrien County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

REGISTERED OF DEEDS
 BERRIEN COUNTY MICHIGAN
 [Signature]

DEC 16 4 02 PM '94

RECORDED

December 12, 1994
 For corners in

<u>Berrien</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8</u> R <u>18</u>	<u>A-1</u>
Common to: <u>T7S, R18W, M13</u>	T _____ R _____	_____
<u>T7S, R19W, M13</u>	T _____ R _____	<u>M-13</u>
<u>T8S, R19W, M1</u>	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Charles W. Barger in a field survey on November, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
0													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.


A. Description of original monument and accessories and/or subsequent restoration:

1829 Lucius Lyon
 80.00 Set frost corner to Townships 7 & 8 South, Ranges 18 & 19 West

Beech 14 N. 68 W. 24.	12/16/94	111#9004	A66
Ash 14 S. 21 E. 41		CORNER	\$9.00
	12/16/94	111#9004	A66
		STATE REMON. FEE	\$2.00

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-1 Found 1/2" iron in Monument Box
 Face of Guy Pole N.40W., 39.3'
 Face of Power Pole N.37E., 36.7'
 Face of Guy Pole S.37E., 31.7'
 Found Nail in 12" Walnut N.40E., 62.4'



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-1 Set 1" pipe (2' long) with 2 1/2" Brass Remonumentation Cap over 1/2" iron in Monument Box
 Set Witness Tag on Guy Pole N.40W., 39.3'
 Set Witness Tag on Power Pole N.37E., 36.7'
 Set Witness Tag on Guy Pole S.37E., 31.7'
 Set Witness Tag in 12" Walnut N.40E., 62.4'

And is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by Charles W. Barger Date December 16, 1994
 Surveyor's Michigan License No. 31589

SOUTHEAST CORNER - SECTION 36-7-19
NORTHEAST CORNER - SECTION 1-8-19
SOUTHWEST CORNER - SECTION 31-7-18
NORTHWEST CORNER - SECTION 6-8-18 (A-1)

10

1829 Lucius Lyon L2. P65 Government Notes

80.00 Set frost corner to Townships 7 & 8 South, Ranges 18
& 19 West

Beech 14 N. 68 W. 24
Ash 14 S. 21 E. 41

Circa 1945 Berrien County Road Commission

T-Rail
Elec. Pole NE 36.2
Elec Guv Pole NW 38.5'
Elec Guv Pole SE 31.5'
6" Walnut N 30 E 72.8'
NE Cor Conc hdwall SW 33.2'
NW Cor Conc hdwall S 10 E 26.0'

JUNE, 1972 E.R. Stefan L935. P687 Recorded Survey

Monument Box
Face PP N. 45 W. 39.0'
Face PP N. 45 E. 36.4'
Face PP S. 45 W. 31.4'

NOV 28, 1994 C.W. Barger

1/2" Iron in Monument Box
Face of Guv Pole N. 40 W. 39.0'
Face of Power Pole N. 37 E. 36.4'
Face of Guv Pole S. 37 E. 31.4'
Found Nail in 12" Walnut N. 40 E. 62.4'

CAVEY &

DEC 7 1995

COMMISSION