

APPROVED BY THE BERRIEN COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 343 OF 1990  
*[Signature]*  
 11-10-98

RECORDED

**BERRIEN COUNTY REMONUMENTATION  
 LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

98 NOV 19 PM 4:48

BERNICE TRETHERWAY  
 REGISTER OF DEEDS  
 BERRIEN COUNTY, MICHIGAN

For corners in <b>BERRIEN COUNTY</b>	Located in: <b>BERTRAND TWP.</b>	Corner Code # <b>(B-9) S1/4 Sec 19 (State Line)</b>
1. Public Land Survey	T <u>8S</u> R <u>17W</u>	<u>B-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No _____ Recorded Plat _____		
5. Private Claims _____		

**Register of Deeds Stamp & File Number**

11/19/98	111#6180	A77
	CORNER	\$7.00
11/19/98	111#6180	A77
	STATE REMON FEE	\$2.00

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, **Alan Bartlett** in a field survey on **November 13 1998** hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
**(No Government Corner Set)**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 No Government corner set. Used Michigan Department of Transportation notes for U.S. 31 (John Corbit, January 10, 1968) to set corner on state line as determined by existing Indiana corners. Government Monument restored with approval of the Berrien County Remonumentation Peer Group of Surveyors on November 10 1998.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Set Concrete Monument with Berrien County Remonumentation Cap in corn field. 50' South of west running fence.  
 Witnesses

S80E	Set Nail and Flasher in 9" Clump Mullberry	76.94'
West	Fnd 1" Iron Pipe	47.63'
N40W	Notch in R.R. Rail fence Post N.E. side	66.00'
N75W	Set Nail and Flasher in N side of 36" Tree	44.92'

This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

Signed by *Alan K. Bartlett* Date 11/17/98  
 Surveyor's Michigan License No. 35988

