

REMONUMENTATION

RECORDED

FEB 17 1994

Dec 28 2 17 PM '93

COMMISSION

BERRIEN COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE 12/28/93

Filing Requirement of Act 74, Mich. P.A. 1970

12/28/93

111#5115 ASS  
CORNER \$7.00  
111#5115 ASS  
STATE REMON FEE \$2.00

For corners in *Berrien County*  
BERRIEN COUNTY, MICHIGAN  
Berrien County

Located in:

Corner Code =#

- 1. Public Land Survey T 8 S. R 17 W. E-9 D-9
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, R.L. Harner, in a field survey on November 11, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-8  
 Iron in mon. box - H.L. Dreher - 1971  
 Center of T.P. N. 45° W. 32.9 ft.  
 Center of 24" maple S. 85° E. 28.5 ft.  
 Iron in mon. Box - Wightman & Assoc. 1974  
 P. pole N. 40° W. 32.81 ft.  
 Iron West 33.00 ft.  
 7" maple S. 40° W. 21.84 ft.

D-9  
 Iron - H.L. Dreher  
 4" Steel fence post East 0.10 ft.  
 In N. & S. fence  
 Iron North 391.9 ft.  
 2644.6 ft. East to S.E. Cor. of Sec. 20

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-9  
 Found P.K. nail over iron pipe 0.9 ft. deep

D-9  
 Found 3/4" iron in concrete, beside 4" Steel fence post

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-9  
 Set 1" x 3' iron pipe with brass cap in monument box  
 5/8" rebar West 16.00 ft.  
 5/8" rebar East 18.61 ft.  
 Nail in power pole N. 20° W. 89.18 ft.  
 Nail in 12" maple S. 85° W. 33.79 ft.  
 Nail in 20" maple N. 30° E. 97.73 ft.

D-9  
 Set brass cap in 3/4" iron in concrete  
 Face of 4" steel post East 0.10 ft.  
 Nail in triple W. Cherry West 3.17 ft.  
 Nail in 10" Elm N. 88° E. 14.40 ft.  
 Nail in twin W. Cherry South 6.86 ft.  
 5/8" rebar N. 45° W. 12.15 ft.

Signed by *[Signature]*

Date December 28, 1993

Surveyor's Michigan License No. 22436

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983