

RECORDED

FEB 17 1994

COMMISSION

DEC 28 2 17 PM '93

BERRIEN COUNTY REMONUMENTATION PROGRAM

LAND CORNER RECORDATION CERTIFICATE 12/28/93

Filing Requirement of Act 74, Mich. P.A. 1970

12/28/93

111#5115 A33  
CORNER \$7.00  
111#5115 A33  
STATE REMON FEE \$2.00

For corners in Berrien Traverse  
Berrien  
REGISTER OF DEEDS  
MICHIGAN

Located In:	Corner Code #
1. Public Land Survey T 8 S. R 17 W.	C-9 F-9
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
2. Property Controlling S _____ T _____ R _____	_____
in Section S _____ T _____ R _____	_____
3. Miscellaneous S _____ T _____ R _____	_____
Property in Sec. S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, R.L. Harner, in a field survey on November 11, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-9  
3/4" pipe in mon. box - M.D.O.T. March 1971  
33" W. Cherry S. 55° W. 123.90 ft.  
Cedar post N. 30° E. 22.68 ft.  
4" steel fence post East 10.88 ft.

F-9  
5/8" iron D.L. Warren 1967  
no witnesses

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-9  
Found 3/4" iron in mon. box

F-9  
Found 5/8" iron

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-9  
Set 1" x 3' iron and brass cap in mon box  
N.W. corner of barn S. 02° E. 72.31 ft.  
N.E. corner of barn S. 60° E. 84.64 ft.  
Nail in P.P. J-111-71 S. 05° W. 99.65 ft.  
Nail in P.P. J-111-70 S. 45° W. 137.89 ft.

F-9  
Set concrete monument with brass cap  
Nail in P.P. J-113-7 S. 88° W. 17.77 ft.  
Nail in 30" oak N. 45° E. 2.57 ft.  
Nail in 8" elm N. 05° W. 24.13 ft.  
S.E. corner of barn N. 40° E. 7.10 ft.

Signed by [Signature]

Date December 28, 1993

Surveyor's Michigan License No. 22436