

**SURVEY &  
REMONUMENTATION**

RECORDED

FEB 17 1994

DEC 28 2 17 PM '93

BERRIEN COUNTY REMONUMENTATION PROGRAM

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

111#5115 A33  
CORNER \$7.00  
111#5115 A33  
STATE REMON FEE \$2.00

For corners in Berrien (County)  
REGISTER OF DEEDS  
BERRIEN COUNTY, MICHIGAN

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

12/28/93

- |                                    |                              |                       |
|------------------------------------|------------------------------|-----------------------|
| 1. Public Land Survey              | T <u>8</u> S. R <u>17</u> W. | <u>G-9</u> <u>H-9</u> |
|                                    | T _____ R _____              | _____                 |
|                                    | T _____ R _____              | _____                 |
|                                    | T _____ R _____              | _____                 |
| 2. Property Controlling in Section | S _____ T _____ R _____      | _____                 |
|                                    | S _____ T _____ R _____      | _____                 |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____      | _____                 |
|                                    | S _____ T _____ R _____      | _____                 |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, R.L. Harner, in a field survey on November 11, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- |                         |  |
|-------------------------|--|
| <u>G-9</u><br>No record | <u>H-9</u><br>Iron 1.6 ft. East of corner - Berrien County Road Commission - no date<br>Fence post East 16.2 ft.<br>Fence post West 16.1 ft.<br>12" oak N.W. 40.0 ft.<br>Iron - R.W. Prestine Aug. 1977<br>Center 36" oak N. 22° W. 40.3 ft.<br>E'ly corner brick wall West 32.7 ft. |
|-------------------------|--|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- |   |                               |
|---|-------------------------------|
| <u>G-9</u><br>Found stone - recently used by others | <u>H-9</u><br>Found 3/4" iron |
|---|-------------------------------|

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |  |  |
|--|--|
| <u>G-9</u><br>Removed stone - set concrete monument with brass cap<br>P.K. nail in 12" maple N. 35° E. 23.50 ft.<br>P.K. Nail in twin ash N. 10° E. 8.70 ft.<br>P.K. nail in 20" maple S. 40° W. 15.25 ft.<br>P.K. nail in 12" maple S. 65° E. 27.73 ft. | <u>H-9</u><br>Set concrete monument with brass cap<br>P.K. nail in P.P. West 29.53 ft.<br>P.K. nail in 40" oak N. 22° W. 39.73 ft.<br>N.E. corner of brick wall S. 50° W. 60.10 ft.<br>P.K. nail in R.R. tie post East 24.40 ft. |
|--|--|

Signed by [Signature] Date December 28, 1993  
Surveyor's Michigan License No. 22436