

DEC 08 1993 LAND CORNER RECORDATION CERTIFICATE  
COMMISSION FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Berrien County Remonumentation

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>Berrien</u> COUNTY T. <u>8</u> N. S., R. <u>17</u> E. W.		<u>I-9</u>
2. PROPERTY CONTROLLING IN SECTION <u>23</u> , T. <u>8</u> N. S., R. <u>17</u> E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS  
BERRIEN COUNTY MICHIGAN

NOV 29 2 08 PM '93

RECORDED

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Robert W. Prestine, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on Nov. 15, 1993, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

I-9 SET. POST, William Brookfield D.S. 1827  
S.W. COR. GOVT. 1.63 EAST of mile post #29  
SEC. 23  
Y. OAK 18" S30°W 39'  
W. " 15" N26 1/2°E 33'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I-9 Found stone, from surveys by H.L. Dreher R.L.S. Dated 1946 & 1947, Berrien Co. Rd. Comm. WITS. Edwin Voss R.L.S. 1967 stone (NO WITS). 1/2" rebar in 1975 Found by R.W. Prestine R.L.S. & from North 547.0'. Iron 10' North & 33' East on survey by Dreher (found) & re-set temp. I-9 Indiana corner west on state line 189.95', Berrien Co. Rd. Comm. iron & stone

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-9 Excavated & Found stone Nov. 18-93, under asphalt Rd. & 5" of gravel. Set 3/4" x 36" pipe & Berrien Co. remonumentation cap bent over stone & set monument box.  
Nail & washer in S. side Elec Pole & m. Hole N37°W 26.23'  
N52°E 42.21'  
& san. m. Hole N26°E 15.25'  
witnessed by Peer Group 11-8-93  
Nail & washer in N. side 12" walnut  
5 50°W 34.8'  
3/8" iron N. 72°E 34.8'

SIGNED BY Robert W. Prestine DATE Nov. 29-93

SURVEYOR'S MICHIGAN REGISTRATION NO. 18662

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

