

RATIFIED BY THE BERRIEN COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990

RECORDED

BERRIEN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

98 OCT 27 PM 1:06

BERNICE TRETHERWAY
REGISTER OF DEEDS
BERRIEN COUNTY, MICHIGAN

[Signature]
4-21-98

For corners in

<u>Berrien</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8S</u> R <u>R17W</u>	<u>M-3</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

10/27/98 111#4092 A44
CORNER \$7.00
10/27/98 111#4092 A44
Register of Deeds Stamp & File Number
STATE REMON FEE \$2.00

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, V. J. Strebs, in a field survey on May 13, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1827 WILLIAM BROOKFIELD, D.S. - SOUTH ON EAST SIDE OF SECTION 1, MEASURED 80 CHAINS, SET POST FOR CORNER TO SECTIONS 1 & 12, T8S, R17W AND SECTIONS 6 & 7, T8W, R16W; 13" WHITE OAK S35½"W 79 LINKS; 8" HICKORY N16½"W 99 LINKS.
- AUGUST 3 & 4, 1885 ALBERT DREW COUNTY SURVEYOR SET STONE, GOVERNMENT WITNESSES STILL STANDING, NEW WITNESS 12" WHITE OAK N15"W 3½ LINKS.
- 1950's DREHER - STONE (NO WITNESSES).
- DECEMBER 22, 1992 R.W. PRESTINE - FOUND SMALL STONE AT FENCE CORNER, REMOVED STONE AND SET CONCRETE MONUMENT.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CONCRETE MONUMENT

SURVEY & REMONUMENTATION

NOV 20 1998

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 4" X 3 FT CONCRETE MONUMENT W/B.C.R.P. BRASS CAP; WIT TAG IN 1" OAK NORTH 8.26°; WIT TAG IN 16" HICKORY N55°E 18.60°; WIT TAG IN 18" TWIN CHERRY S85°E 9.67°; WIT TAG IN R.R. TIE FENCE POST S20°W 1.21°.

ACCEPTED AS A CAREFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *[Signature]*
Surveyor's Michigan License No. 26469



Date 7-9-98

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1993
REVISED OCT., 1995