

SURVEY & REMONUMENTATION
 DEC 08 1993
 COMMISSION

11/29/93 111#2893 A33
 CORNER \$7.00
 11/29/93 111#2893 A33
 STATE REMON FEE \$2.00

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Berrien County Remonumentation

FOR CORNERS OF: Berrien COUNTY LOCATED IN--

	T.	N. S.	R.	E. W.	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	<u>8</u>	<u>17</u>			<u>M-9</u>
2. PROPERTY CONTROLLING IN SECTION <u>24</u>	<u>8</u>	<u>17</u>			
3. MISCELLANEOUS PROPERTY IN SECTION _____					
4. LOT NO. _____, RECORDED PLAT _____					
5. PRIVATE CLAIMS _____					

RECORDED
 NOV 29 2 09 PM '93
 REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Robert W. Prestine, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on OCT. 29, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

M-9 Post, W.M. Brookfield D.S. 1827
 SE. COR.
 SEC. 24 40.84 Chs. intersected IND. STATE LINE 3.40 Chains
 East of mile post 31.
 W. OAK 7" N61°W 51
 Y. " 10" N35°E 27

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

M-9 Found standard Cass County monument, Alum. Cap. & Alum. rod with magnet. Set under Cass Co. remon project 1975±.
 used corner as set several times, also used by others. as Berrien & Cass Co. Line & STATE LINE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-9 Used same corner as above, did NOT remove cor. as orig. set for Cass Co. ratified by peer group to use NOT remove.
 NOV. 8-1993 - set man. Box over.
 Nail & washer in 16" thick. 512°W 30.89'
 " " " Elec. & Tele Pole N21°W 7.34'
 " " " 26" Hick N32°E 42.148'
 " " " 14' Cedar N72°E 45.15'
 12" Nail & STATE LINE Rd. as CONST.
 54'W. Chain LINK to South, 36.56'
 steel fe. Post North 10.1'
 ratified by peer group 11-8-93

SIGNED BY Robert W. Prestine DATE NOV. 29-93

SURVEYOR'S MICHIGAN REGISTRATION NO. 18662

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
 CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
 MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

