



NORTHWEST CORNER SECTION 18-8-18  
SOUTHWEST CORNER SECTION 7-8-18  
95512.05

(Bertrand Township - Buffalo & Mt. Zion Rd)

Jul 1829

L. Lyon L. 2, P. 118-19 Government Notes

South on East boundary of Sec 12 T8S R19W  
80.00 Set frost corner to Secs 12 & 13  
Ash 8 N14W 58  
Beech 7 S21W 34

Feb 1830

L. Lyon L. 2, P. 122 Government Notes

West on random between 7 & 18  
79.98 Intersected W. Boundary 20 lks South of post  
East Corrected the line between 7 & 18

UNKNOWN

Berrien County Road Commission

Cap

Iron South 33.0'  
6" Ash N 70° W 45.3'  
16" Chestnut SW 85.2'  
Iron N. 33'

UNKNOWN

R. Prestine

Plug by B.C.R.C.  
1/2" Iron bar S. 5° E. 33.8'  
Face R.R. Tie cor. post North 46.75'  
Center of E. Pole S. 2° E. 36.6'  
Center of 48" Pine S. 56° W. 98.4'

May, 1995

C. Barger

Found BCRC Cap

Found Iron South 33.0'  
Set Witness Tag in PP #B676-14 S. 5° 48' E. 36.61'  
Set Witness Tag in PP #B646-33 N. 10° 44' W. 85.55'  
Center of Telephone Pedestal N. 12° 42' E. 38.43'  
Center of Telephone Pedestal N. 75° 47' W. 99.91'  
Found 1 1/4" Iron Rod N. 0° 51' W. 34.83' (Bent)