

REMONUMENTATION

APR 26 1995

RECORDED

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Nov 21 10 37 AM '94

Register of Deeds Stamp & File Number

RATIFIED BY THE BERRIEN COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990

Signature and date 11/08/94

Berrien County Remonumentation

Located In: Corner Code #

Berrien (County)

- 1. Public Land Survey T 8 S R 18 W G-9
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

I, Robert W. Prestine, in a field survey on November 15, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-9 Southwest corner, Section 22, T.8 S; R.18 W;

11/21/94

111#7352 A66 CORNER \$7.00
11/21/94 111#7352 A66 STATE REMON FEE \$2.00

On Indiana-Michigan State line
Government wits. gone
Lucious Lyons Nov. 10, 1835 wood post
Hickory 13" N 81° W 1.77 chains
Hickory 12" N 18 1/2° W 2.12 chains

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-9
Did not find corner-R.R. tie corner post near
Set corner as per description of Lakehead Pipeline Company as described in Liber 852, Pages 317, 318 & 319, in line with 6" concrete posts set by W.P.A. in 1938 for Northeast and Northwest corners of Section 10, T.38 N; R.1 E; State of Indiana

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-9
Set 4" round Berrien County Remonumentation monument
Nw. cor. house S 7° W 73.7'
Ne. cor. house S 56° E 78.2'
Nail & wit. tag in North side 17" burr oak East 89.7'
Face conc. foundation grain bin West 110.1'

This position is accepted as a careful and faithful reestablishment of the position of the original corner.

Signed by Robert W. Prestine Date November 16, 1994

Surveyor's Michigan License No. 18662

