

SURVEY & REMONUMENTATION

APR 26 1995

RECORDED

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Nov 21 10 37 AM '94
Filing Requirement of Act 74, Mich. P.A. 1970
Berrien County Remonumentation

Bernice T. ... REGISTER OF DEEDS BERRIEN COUNTY MICHIGAN

Register of Deeds Stamp & File Number

RATIFIED BY THE BERRIEN COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990

11/08/94 For corners in Berrien (County)

Located In: Corner Code #

Table with 3 columns: Description, T, S, R, W, and Corner Code. Includes rows for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

4. Lot No. , Recorded Plat
5. Private Claims

I, Robert W. Prestine, in a field survey on November 15, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-9 South Quarter corner, Section 22, T.8 S; R.18 W;
On Indiana-Michigan State Line
Not set by Government
No record of corner found or set by others

11/21/94 111#7352 A66
CORNER \$7.00
11/21/94 111#7352 A66
STATE REMON FEE \$2.00


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-9
Found old 1" iron pipe on East side of 6" square concrete post in line with North and West tree rows
902.65' East of 6" concrete post set by W.P.A. in 1938 for Northeast corner of Section 10, T.38 N; R.1 E; State of Indiana

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-9
Set 4" round Berrien County Remonumentation monument in place
Nail & wit. tag in West side 24" walnut South 6.00'
Nail & wit. tag in East side 15" walnut N 5° W 12.17'
Nail & wit. tag in South side 17" walnut S 85° W 3.88'
0.25' East & 0.10' North of Southeast corner 6" concrete post

This position was not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.



Signed by Robert W. Prestine Date November 16, 1994

Surveyor's Michigan License No. 18662