

ATIFIED BY THE BERRIEN COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER MICHIGAN
PUBLIC ACT 345 OF 1990

RECORDED

BERRIEN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

98 OCT 27 PM 1:06
BERNICE TRETHERWAY
REGISTER OF DEEDS
BERRIEN COUNTY, MICHIGAN

For corners in _____
Berrien (County) Located In: _____ Corner Code # _____

- 1. Public Land Survey T 8S R19W B-9
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

10/27/98 111#4092 A44
CORNER \$7.00
10/27/98 111#4092 A44
Register of Deeds State of Michigan No. 42.00

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, V. J. Strebs, in a field survey on May 12, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

NOT SET IN ORIGINAL SURVEYS

- 1983 STEFAN-STREBS RLSPC - FOUND STONE IN E-W FENCE LINE, FENCE NORTH
NAIL IN 30" MAPLE N45°E 22.73'
NAIL IN 15" MAPLE S80°E 35.82'
NAIL IN 24" MAPLE SOUTH 53.45'
- 1992 PIERCE & ASSOCIATES - FOUND STONE (NO WITNESSES)
- 1995 WIGHTMAN & ASSOCIATES, INC. - FOUND STONE
PK NAIL IN WOOD FENCE POST N80° E 3.67'
PK NAIL IN 5" TWIN MAPLE NORTH 4.12'
PK NAIL IN 10" MAPLE S25°E 24.58'
PK NAIL IN 15" MAPLE S80°E 35.90'

SURVEY &
REMONUMENTATION

NOV 20 1998

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND STONE IN E-W FENCE LINE, FENCE NORTH

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 4" X 3 FT CONCRETE MONUMENT WITH A B.C.R.P. BRASS CAP. WIT TAG IN 10" TULIP S15°E 24.52'; WIT TAG IN WOOD FENCE POST N85°E 3.52'. WIT TAG IN 18" MAPLE S80°E 35.75; WIT TAG IN 8" TWIN MAPLE NORTH 4.07'; FOUND REBAR N68°W 80.66'; FOUND IRON PIPE AT N.W. COR SEC 8, T38N, R1W, INDIANA PRINCIPAL MERIDIAN - WEST - 138.59'. THIS POSITION NOT ESTABLISHED BY ORIGINAL GOVERNMENT SURVEYORS - THIS MONUMENT IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.

Signed by [Signature]
Surveyor's Michigan License No. 26469



Date 7-9-90

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 26, 1971
REVISED MAY 14, 1975
REVISED JAN. 1963
REVISED OCT., 1965