

RATIFIED BY THE BERRIEN COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER MICHIGAN
PUBLIC ACT 345 OF 1990

RECORDED

**BERRIEN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

99 OCT 27 PM 1:06

BERNICE TRETHERWAY
REGISTER OF DEEDS
BERRIEN COUNTY, MICHIGAN

For corners in

Barrien
(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>8S</u> R <u>19W</u> | <u>C-9</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling
in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

10/27/98 111#4092 A44
Register of Deeds Stamp & File Number \$7.00
10/27/98 111#4092 A44
STATE REMON FEE \$2.00

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, V. J. Strebs, in a field survey on May 12, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1830 LUCIUS LYON D.S.
SOUTH BETWEEN SECTIONS 19 & 20, MEASURED 53.00 CHAINS TO SOUTH BOUNDARY 8.5 CHAINS EAST OF 14 MILE POST.
SET POST 18" BEECH N56°W 9 LINKS; 24" SUGAR N86°E 52 LINKS.
- 1957 H.L. DREHER - STONE IN E-W FENCE 864.5' SOUTH OF W ¼ COR; 4' ELM SOUTH 12.5'; 14" ELM S.E. 19.3'; 6" HICKORY EAST 10.9'; 14" HICKORY S80°W 45.3'
- 1984 R.W. PRESTINE - FOUND STONE; STONE & IRON EAST 7.3'; HICKORY S80°W 45.3'; NAIL IN 24" MAPLE S.E. 28.45'; NAIL IN 22" BASSWOOD SOUTH 25.10'; NAIL IN 26" BASSWOOD S.W. 20.15'.

SURVEY &
REMONUMENTATION

JAN 12 1999

SECTION


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND STONE IN E-W FENCE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 4" X 3 FT CONCRETE MONUMENT WITH A B.C.R.P. BRASS CAP.
IRON PIPE - EAST 7.31'; IRON PIPE AT N ¼ COR SEC 8, T38N, R1W INDIANA PRINCIPAL MERIDIAN - WEST 148.65'
WIT TAG IN 3" ASH S20°E 3.92'; WIT TAG IN 6" ELM S75°E 19.99".
ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by _____
Surveyor's Michigan License No. 26469



Date 7-9-98

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995