

RAIIFIED BY THE BERRIEN COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990

RECORDED

BERRIEN COUNTY REMONUMENTATION 98 OCT 27 PM 1:06
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

BERNICE TRETHERWAY
 REGISTER OF DEEDS
 BERRIEN COUNTY, MICHIGAN

For corners in 4-21-98

_____ Berrien _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8S</u> R <u>R19W</u>	<u>D-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

10/27/98 111#4092 A44
 CORNER \$7.00
 10/27/98 111#4092 A44
 STATE REMON FEE \$2.00
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, V. J. Strebs, in a field survey on May 12, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
 NOT SET IN ORIGINAL SURVEYS.

SURVEY & REMONUMENTATION

JAN 12 1999

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

NO EVIDENCE OF A SUBSEQUENT CORNER BEING SET NOR WAS ONE FOUND; SET BY SINGLE PROPORTIONATE MEASUREMENT USING THE N.E. CORNER SECTION 8, T38N, R1W, INDIANA PRINCIPAL MERIDIAN AND THE S.W. CORNER, SECTION 19, T8S, R19W FOR LINE AND PROPORTIONING THE MEASUREMENT (8, 030.43 FT) BETWEEN THE S.W. CORNER, SECTION 19, T8S, R19W AND THE S 1/4 CORNER, SECTION 21, T8S, R19W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 4" X 3 FT CONCRETE MONUMENT W/B.C.R.P. BRASS UNDER FALLEN BEECH TREE TRUNK. WIT TAG IN 12" BEECH S15°W 27.50; WIT TAG IN 12" BEECH WEST 26.11; WIT TAG IN 8" OAK N50° W - 38.98; WIT TAG IN 16" MAPLE N 45° E 38.08'. - STONE AT N.E. CORNER SECTION 8, T38N, R1W, INDIANA PRINCIPAL MERIDIAN - WEST - 310.21'. THIS PORTION NOT ESTABLISHED BY ORIGINAL GOVERNMENT SURVEYORS. THIS MONUMENT IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.

Signed by _____
 Surveyor's Michigan License No. 26469



Date 7-9-98

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN, 1993
 REVISED OCT, 1995

H:\MONTAVANKAMER\STREBS\LORNO-9.REC