

RAITIFIED BY THE BERRIEN COUNTY  
SURVEY PEER GROUP AS THE  
OFFICIAL CORNER UNDER MICHIGAN  
PUBLIC ACT 345 OF 1990

RECORDED

**BERRIEN COUNTY REMONUMENTATION 98 OCT 27 PM 1:06**  
**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

BERNICE TRETHERWAY  
REGISTER OF DEEDS  
BERRIEN COUNTY, MICHIGAN

For corners in

<u>Berrien</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8S</u> R <u>R19W</u>	<u>E-9</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

10/27/98 111#4092 A44  
CORNER \$7.00  
10/27/98 111#4092 A44  
Register of Deeds Stamp & File Number  
STATE REMON FILE \$2.00

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, V. J. Strebs, in a field survey on May 12, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

FEB. 13, 1830 LUCIUS LYON, D.S.  
FROM N.E. COR SEC 20, T8S, R19W  
MEASURED 52.35 CHAINS SOUTH  
SET POST ON SOUTH SIDE OF SMALL LAKE ON SOUTH BOUNDARY OF SECTION 10.05 CHAINS EAST OF 15TH MILE POST  
4" WILLOW N42°W 18 LINKS  
6" ELM N22° E 13 LINKS

SURVEY &  
REMONUMENTATION

JAN 12 1999

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

CORNER DETERMINED LOST, RESET BY SINGLE PROPORTIONATE MEASUREMENT USING A FOUND STEEL FENCE POST 98.58 FEET WEST FLUSH TO GROUND WITH A WOODEN STAKE NEXT TO IT AND THE SOUTH ¼ CORNER OF SEC 21-T8S-R19W FOR LINE AND PROPORTIONING THE MEASUREMENT 8,030.43 FT) BETWEEN THE S.W. COR SEC 19-T8S-R19W AND THE SOUTH ¼ COR SEC 21-T8S-R19W GALIEN TOWNSHIP.

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 4" X 10 FT PVC PIPE WITH A 1" X 5 FT IRON PIPE WITH A B.C.R.P. BRASS CAP SET IN CONCRETE IN SWAMP ON S.W. SIDE OF SMALL LAKE. WIT TAG IN MAPLE CLUSTER S25°W 31.05'. WIT TAG IN 12" ELM S15°E 71.15'. STEEL FENCE POST FLUSH TO GROUND WEST 99.58'. N ¼ COR SEC 9, T38N, R1W INDIANA PRIME MERIDIAN - WEST - 322.52' IS ACCEPTED AS A CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

Signed by [Signature]  
Surveyor's Michigan License No. 26469



Date 7-9-98

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN, 1983  
REVISED OCT, 1995