

ATIFIED BY THE BERRIEN COUNTY  
 SURVEY PEER GROUP AS THE  
 OFFICIAL CORNER UNDER MICHIGAN  
 PUBLIC ACT 845 OF 1990  
[Signature]  
 4-21-98

RECORDED

98 OCT 27 PM 1:07

**BERRIEN COUNTY REMONUMENTATION  
 LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

BERTHIE TRETHERWAY  
 REGISTER OF DEEDS  
 BERRIEN COUNTY, MICHIGAN

or corners in \_\_\_\_\_

\_\_\_\_\_ Berrien \_\_\_\_\_ Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

Public Land Survey T 8S R 19W H-9  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

10/27/98	111#4092	A44
	CORNER	\$7.00
10/27/98	111#4092	A44
Register of Deeds Stamp Fee Number 2.00		

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 Private Claims \_\_\_\_\_

V. J. Strebs, in a field survey on May 12, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land and Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4		3		2		1
3													
4	7			8			9		10		11		12
5													
6	18			17			16		15		14		13
7													
8	19			20			21		22		23		24
9													
10	30			29			28		27		26		25
11													
12	31			32			33		34		35		36
13													

Description of original monument and accessories and/or subsequent restoration:

- NOT SET IN ORIGINAL SURVEYS
- SEPT 6, 7, 8 & 9, 1886 ALBERT L. DREW, COUNTY SURVEYOR, DOES NOT SHOW CORNER AS SET ON SURVEY MAP, BUT SHOWS DIMENSION OF 40.38 CHAINS FROM S.E. COR. & S.W. COR.
  - 1975 BERRIEN COUNTY ROAD COMMISSION (MONUMENT BOX); IRONS NORTH 50.0' & 75.00'; IRON SOUTH 26.00'
  - JUNE 19., 1990 WIGHTMAN & ASSOCIATES, INC. - FOUND 3/4" IRON ROD IN MON. BOX; PK NAIL IN P.P. S20°E 26.80'; PK NAIL IN R.R. TIE FENCE POST N20°W 30.56'; TOP CENTER OF TELEPHONE RISER BOX NORTH 26.60'.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" IRON ROD IN MONUMENT BOX.

SURVEY &  
 REMONUMENTATION

NOV 20 1998

SECTION

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 1" X 3 FT IRON PIPE W/B.C.R.P. BRASS CAP IN MONUMENT BOX; WIT TAG IN P.P. S15°E 26.81'; WIT TAG IN 12" ELM N10°E 38.82'; WIT TAG IN 10" CHERRY N10°W 44.22'; WIT TAG IN 24" OAK N50°W 62.65'.

THIS POSITION NOT ESTABLISHED BY ORIGINAL GOVERNMENT SURVEYORS. THIS MONUMENT IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.

signed by [Signature]  
 Surveyor's Michigan License No. 26469



Date 7-9-98

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN, 1985  
 REVISED OCT., 1985